

1 LOCATION OF WATER WELL: Sedgwick		FRACTION SE 1/4 SE 1/4 SW 1/4		SECTION NUMBER 27	TOWNSHIP NUMBER T 27 S		RANGE NUMBER R 4W E/W		
Distance and direction from nearest town or city street address of well if located within city? 35000 W. 4th N. Garden Plain, Kansas									
2 WATER WELL OWNER: SIEWART, Joe		RR#,ST. ADDRESS,BOX #: 35000 W. 4th N.							
CITY, STATE: Garden Plain, Kansas		ZIP CODE: 			Application Number: 				
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: 100 ft. ELEVATION: Depth of groundwater Encountered: _____ ft. WELL'S STATIC WATER LEVEL 30 FT. BELOW LAND SURFACE MEASURED ON 8/7/04 Pump test data: Well water was _____ ft. after _____ hours of pumping @ _____ gpm Est. Yield: _____ gpm Well water was _____ ft. after _____ hours of pumping @ _____ gpm Bore Hole Diameter 12 in. to 100 ft. and _____ in. to _____ ft. WELL WATER TO BE USED AS: ☒ 1. Domestic ☐ 3. Feedlot ☐ 5. Public water supply ☐ 7. Lawn and garden only ☐ 9. Dewatering ☐ 11. Injection well ☐ 2. Irrigation ☐ 4. Industrial ☐ 6. Oil field water supply ☐ 8. Air conditioning ☐ 10. Monitoring well ☐ 12. Other (Specify below) Was a chemical/bacteriological sample submitted to Department? YES ☒ NO ; If yes, what mo/day/yr was sample submitted _____ Was Water Well Disinfected? ☒ YES ☐ NO							
5 TYPE OF CASING USED: 1. Steel 3. RPM (SR) 5. Wrought Iron 7. Fiberglass 9. Other (Specify below) CASING JOINTS: ☒ Glued Threaded 2. PVC 4. ABS 6. Asbestos-Cement 8. Concrete tile SDR-26 Welded Clamped Blank casing diameter 5 in. to 45 ft., Dia. _____ in. to _____ ft., Dia. _____ in. to _____ ft. Casing height above land surface: 18 in., Weight: 2.35 lbs. / ft. Wall thickness or gauge No. .214 TYPE OF SCREEN OR PERFORATION MATERIAL: 1. Steel 3. Stainless Steel 5. Fiberglass ☒ 7. PVC 9. ABS 11. Other (specify) 2. Brass 4. Galvanized 6. Concrete Tile 8. RMP (SR) 10. Asbestos-Cement 12. None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1. Continuous slot 3. Mill slot 5. Gauzed wrapped 7. Torch cut 9. Drilled holes 11. None (open hole) 2. Louvered shutter 4. Key punched 6. Wire wrapped ☒ 8. Saw cut 10. Other (specify) SCREEN - PERFORATION INTERVAL From 45 ft. to 100 ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From 24 ft. to 100 ft., From _____ ft. to _____ ft.									
6 GROUT MATERIALS: 1. Neat cement 2. Cement Grout 3. Bentonite Other bentonite hole plug Grout Intervals: From 4 ft. to 24 ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft. What is the nearest source of possible contamination: 1. Septic tank 4. Lateral lines 7. Pit privy 10. Livestock pens 13. Insecticide storage 15. Oil well/Gas well 2. Sewer lines 5. Cess Pool 8. Sewage lagoon 11. Fuel storage 14. Abandon water well 16. Other (specify below) 3. Watertight sewer line 6. Seepage pit 9. Feed yard 12. Fertilizer storage None Apparent Direction from well? _____ How many feet? _____									
From To LITHOLOGIC LOG		From To LITHOLOGIC LOG		RECEIVED AUG 19 2004 BUREAU OF WATER					
0	4	topsoil							
4	15	sandy clay							
15	25	fine sand							
25	35	sandy clay							
35	94	red shale							
94	100	grey shale							
7 Contractor's or Landowner's Certification: This water well was 1. ☒ constructed 2. ☐ reconstructed or 3. ☐ plugged under my jurisdiction and was completed on (mo/day/year) 8/7/2004 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This water well record was completed on (mo/day/year) 8/9/2004 under the business name of Harp Well & Pump Service Inc. by (signature) <i>Jo dd S. Harp</i>									