

1 LOCATION OF WATER WELL: Sedgwick		FRACTION NW 1/4 NW 1/4 NE 1/4	SECTION NUMBER 36	TOWNSHIP NUMBER T 27 S	RANGE NUMBER R 4W E/W																											
Distance and direction from nearest town or city street address of well if located within city? 31743 W. Harry Garden Plain, Kansas																																
2 WATER WELL OWNER: RR#,ST. ADDRESS,BOX #: CITY, STATE:		ROBEY, George J. ETUX 31743 W. Harry Garden Plain, Kansas Board of Agriculture, Division of Water Resource Application Number:																														
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: N +-----+ X +-----+ NW NE SW SE S		4 DEPTH OF COMPLETED WELL: 100 ft. ELEVATION: Depth of groundwater Encountered: _____ ft. WELL'S STATIC WATER LEVEL 40 FT. BELOW LAND SURFACE MEASURED ON mo/day/yr: 12/5/09 Pump test data: Well water was _____ ft. after _____ hours of pumping @ _____ gpm Est. Yield: _____ gpm Well water was _____ ft. after _____ hours of pumping @ _____ gpm Bore Hole Diameter 12 in. to 100 ft. and _____ in. to _____ ft. WELL WATER TO BE USED AS: ☒ Domestic ☐ Feedlot ☐ Public water supply ☐ Lawn and garden only ☐ Dewatering ☐ Injection well ☐ Irrigation ☐ Industrial ☐ Oil field water supply ☐ Air conditioning ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? YES ☒ NO ☒ ; If yes, what mo/day/yr was sample submitted _____ Was Water Well Disinfected? ☒ YES ☐ NO																														
5 TYPE OF CASING USED: 1. Steel 3. RPM (SR) 5. Wrought Iron 7. Fiberglass 9. Other (Specify below) ☒ 2. PVC ☐ 4. ABS ☐ 6. Asbestos-Cement ☐ 8. Concrete tile SDR-26 Blank casing diameter 5 in. to 30 ft., Dia. _____ in. to _____ ft., Dia. _____ in. to _____ ft. Casing height above land surface: 12 in., Weight: 2.35 lbs. / ft. Wall thickness or gauge No. .214 TYPE OF SCREEN OR PERFORATION MATERIAL: 1. Steel 3. Stainless Steel 5. Fiberglass ☒ 7. PVC 9. ABS 11. Other (specify) 2. Brass 4. Galvanized 6. Concrete Tile 8. RMP (SR) 10. Asbestos-Cement 12. None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1. Continuous slot 3. Mill slot 5. Gauzed wrapped 7. Torch cut 9. Drilled holes 11. None (open hole) 2. Louvered shutter 4. Key punched 6. Wire wrapped ☒ 8. Saw cut 10. Other (specify) SCREEN - PERFORATION INTERVAL From 30 ft. to 100 ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From 24 ft. to 100 ft., From _____ ft. to _____ ft.																																
6 GROUT MATERIALS: 1. Neat cement 2. Cement Grout 3. Bentonite Other bentonite hole plug Grout Intervals: From 4 ft. to 24 ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft. What is the nearest source of possible contamination: ☒ 1. Septic tank 4. Lateral lines 7. Pit privy 10. Livestock pens 13. Insecticide storage 15. Oil well/Gas well ☐ 2. Sewer lines 5. Cess Pool 8. Sewage lagoon 11. Fuel storage 14. Abandon water well 16. Other (specify below) ☐ 3. Watertight sewer line 6. Seepage pit 9. Feed yard 12. Fertilizer storage Direction from well? West How many feet? 50 ft. plus																																
LITHOLOGIC LOG <table border="1" style="width:100%; border-collapse: collapse;"><thead><tr><th>From</th><th>To</th><th>LITHOLOGIC LOG</th></tr></thead><tbody><tr><td>0</td><td>3</td><td>topsoil</td></tr><tr><td>3</td><td>10</td><td>clay</td></tr><tr><td>10</td><td>15</td><td>sandy clay</td></tr><tr><td>15</td><td>22</td><td>fine sand</td></tr><tr><td>22</td><td>45</td><td>medium shale</td></tr><tr><td>45</td><td>60</td><td>gray shale</td></tr><tr><td>60</td><td>70</td><td>red shale</td></tr><tr><td>70</td><td>100</td><td>grey shale</td></tr></tbody></table>						From	To	LITHOLOGIC LOG	0	3	topsoil	3	10	clay	10	15	sandy clay	15	22	fine sand	22	45	medium shale	45	60	gray shale	60	70	red shale	70	100	grey shale
From	To	LITHOLOGIC LOG																														
0	3	topsoil																														
3	10	clay																														
10	15	sandy clay																														
15	22	fine sand																														
22	45	medium shale																														
45	60	gray shale																														
60	70	red shale																														
70	100	grey shale																														
7 Contractor's or Landowner's Certification: This water well was 1. ☒ constructed 2. reconstructed or 3. plugged under my jurisdiction and was completed on (mo/day/year) 12/5/2009 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This water well record was completed on (mo/day/year) 12/10/2009 under the business name of Harp Well and Pump Service by (signature) Todd S. Harp																																