

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Sedg.</u>	Fraction <u>SW 1/4 SW 1/4 SW 1/4</u>	Section number <u>36</u>	Township number <u>T 27 S</u>	Range number <u>R 4 E</u>
2. Distance and direction from nearest town or city: <u>2 West Garden Plain Ks and</u> Street address of well location if in city: <u>1 mile South</u>		3. Owner of well: <u>Harvey Robben</u> R.R. or street: <u>RR</u> City, state, zip code: <u>Cheney Ks 67025</u>				
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: <u>x-Well</u> <u>house</u>		6. Bore hole dia. <u>11</u> in. Completion date <u>10/24/77</u> Well depth <u>61</u> ft.		
5. Type and color of material		From	To	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
<u>Top soil</u>		<u>0</u>	<u>4</u>	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
<u>Red clay.</u>		<u>4</u>	<u>13</u>	9. Casing: Material <u>PVC</u> Weight: <u>above</u> or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☒ Weight <u>2.31</u> lbs./ft. Dia. <u>3</u> in. to <u>61</u> ft. depth Well Thickness: inches <u>4</u> Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>1214</u>		
<u>med. sand.</u>		<u>13</u>	<u>18</u>	10. Screen: Manufacturer's name <u>M.P.I.</u> Type <u>PVC</u> Dia. <u>5 1/2</u> Slot/auze <u>1/16</u> Length <u>25 ft.</u> Set between <u>36</u> ft. and <u>61</u> ft. <u> </u> ft. and <u> </u> ft. Gravel pack? ☒ Size range of material <u>3/8</u>		
<u>Blue green shale</u>		<u>18</u>	<u>29</u>	11. Static water level: <u>18</u> ft. below land surface Date <u>10/24/77</u> mo./day/yr.		
<u>Reddish shale</u>		<u>29</u>	<u>54</u>	12. Pumping level below land surfaces: <u>31</u> ft. after <u>1/2</u> hrs. pumping <u>15</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>40</u> g.p.m.		
<u>Blue-green shale.</u>		<u>54</u>	<u>61</u>	13. Water sample submitted: <u> </u> mo./day/yr. ☐ Yes ☒ No Date <u> </u>		
				14. Well head completion: <u> </u> Pitless adapter <u>12</u> inches above grade		
				15. Well grouted? <u>yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>3</u> ft. to <u>13</u> ft.		
				16. Nearest source of possible contamination: <u>Feed</u> ft. <u>350</u> Direction <u>East</u> Type <u>LOT</u> Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: Manufacturer's name <u> </u> ☒ Not installed Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:		(Use a second sheet if needed)		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Weninger Drilling 318</u> Business name <u>ATI Colwich</u> License No. <u> </u> Address <u> </u> Signed <u>J. Weninger</u> Date <u>10/24/77</u> Authorized representative		
19. Remarks: <u>Customer to furnish</u> <u>4x4x4 reinforced slab</u> <u>at top of well</u>						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5