

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 094 STANTON SE 1/4 SE 1/4 NE 1/4 34 T 27 S R 40 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 5.5 MILES NORTH AND 4 MILES EAST OF JOHNSON.

2 WATER WELL OWNER: H & C FARMS INC.  
 RR#, St. Address, Box #: R.R. 1 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: JOHNSON, KS 67855- Application Number: 24494

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 619 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 217 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 217 ft. below land surface measured on mo/day/yr 12/09/91  
 Pump test data: Well water was 494 ft. after 4 hours pumping 919 gpm  
 Estimated Yield 800 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 24 in. to 619 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 02 IRRIGATION  
 Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 619 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT  
 SCREEN PERFORATED INTERVALS: From 259 ft. to 619 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 619 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? SOUTH How many feet? 100

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	01 CLAY			
4	15	07 FINE SAND			
15	38	01 CLAY 07 FINE SAND			
38	58	06 VERY FN SAND 07 FINE SAND 01 CLAY			
58	65	07 FINE SAND 08 MEDIUM SAND			
65	92	01 CLAY			
92	120	05 SAND 13 FINE GRAVEL			
120	135	01 CLAY 28 ROCK			
135	143	07 FINE SAND			
143	155	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/05/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/05/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas A. Henkle*

