

1 LOCATION OF WATER WELL: ; Fraction ; Section Number ; Township Number ; Range Number
 COUNTY: 094 STANTON ; NE 1/4 NW 1/4 SE 1/4 ; 15 ; T 27 S ; R 41 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 8 1/2 MILES NORTH, & 1/3 WEST OF JOHNSON

2 WATER WELL OWNER: WINGER, MELVIN
 RR#, St. Address, Box #: RR 1 BOX 88 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : JOHNSON, KS 67855- Application Number: 27,250

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: ; 4 DEPTH OF COMPLETED WELL 615 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 177 ft. below land surface measured on mo/day/yr 05/01/98
 Pump testdata: Well water was 495 ft. after 4 hours pumping 820 gpm
 Estimated Yield 820 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 615 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 615 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 222 ft. to 612 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 615 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHWEST How many feet? 272

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	25	04 SANDY CLAY 31 CALICHE			
25	38	01 CLAY 05 SAND			
38	66	04 SANDY CLAY 31 CALICHE			
66	95	05 SAND 01 CLAY			
95	110	04 SANDY CLAY			
110	126	04 SANDY CLAY 05 SAND			
126	165	04 SANDY CLAY			
165	181	04 SANDY CLAY 05 SAND			
181	222	04 SANDY CLAY 20 LIMESTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/29/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/12/98 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL: : Fraction : Section Number : Township Number : Range Number
 COUNTY: 094 STANTON : NE 1/4 NW 1/4 SE 1/4 : 15 : T 27 S : R 41 W

2 WATER WELL OWNER: WINGER, MELVIN
 RR#, St. Address, Box #: RR 1 BOX 88 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : JOHNSON, KS 67855- Application Number: 27,250

FROM	TO	LITHOLOGIC LOG
222	237	05 SAND 01 CLAY
237	263	04 SANDY CLAY 05 SAND
263	289	23 SANDSTONE 31 CALICHE
289	332	19 SHALE 20 LIMESTONE
332	343	19 SHALE 20 LIMESTONE 23 SANDSTONE
343	367	19 SHALE 23 SANDSTONE 20 LIMESTONE
367	378	23 SANDSTONE 19 SHALE 20 LIMESTONE
378	400	23 SANDSTONE 31 CALICHE
400	408	20 LIMESTONE
408	420	31 CALICHE 23 SANDSTONE
420	433	23 SANDSTONE 31 CALICHE 20 LIMESTONE
420	433	01 CLAY
433	455	31 CALICHE 23 SANDSTONE 19 SHALE
455	469	23 SANDSTONE 31 CALICHE 01 CLAY
469	471	20 LIMESTONE
471	483	31 CALICHE 23 SANDSTONE 01 CLAY
483	497	31 CALICHE 23 SANDSTONE 01 CLAY
497	541	23 SANDSTONE 31 CALICHE 01 CLAY
541	569	23 SANDSTONE 31 CALICHE 01 CLAY
541	569	23 SANDSTONE 31 CALICHE 01 CLAY
541	569	20 LIMESTONE
569	591	23 SANDSTONE 31 CALICHE 20 LIMESTONE
569	591	01 CLAY
591	600	31 CALICHE 01 CLAY 19 SHALE
600	612	23 SANDSTONE 31 CALICHE
612	637	31 CALICHE 19 SHALE
637	650	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/29/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/12/98 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Richman*