



# DRILLERS TEST LOG

CUSTOMERS NAME Lee Raney DATE 12-10-87  
STREET ADDRESS Box 372 TEST # 1 E. LOG yes  
CITY & STATE Johnson, KS 67855 DRILLER Livingston  
COUNTY Stanton QUARTER SW SECTION 12 TOWNSHIP 27 RANGE 41 Stanton  
LOCATION \_\_\_\_\_ WELL LOCATION \_\_\_\_\_

%	FOOTAGE			DESCRIPTION OF STRATA	Static Water Level
	From	Pay	To		Proposed Well Depth
	0		2	Top Soil	100
	2		22	Brown, Sandy Clay	400
	22		25	Sand, fine to med.	
	25		33	Brown, sandy clay	
	33		53	Sand, fine to med.	
	53		65	Brown, sandy clay	
	65		71	Brown, sandy clay with fine sand streaks	
	71		187	Brown, sandy clay	
60	187	4	191	Sand, fine to med., coarse and small, brown gravel	
	191		200	Brown, sandy clay	
	200		217	Brown, sandy clay, limerock	
15	217	20	237	Soap stone and sand stone	
25	237	19	256	Sand stone and soap stone, used water, mud thick	
15	256	11	267	Yellow soap stone and sand stone streaks	
	267		356	Weathered shale and lime stone ledges, hard in places	
	356		380	Soap stone	
	380		400	Shale and lime stone and soap stone	
				Total Depth - 267	
				5" PVC	
				Perf	Plain
				267-217' 50'	
				217-195	22'
				195-185 10'	
				185-0	185'
				TOTAL 60'	207'
				4 - 50# Hi-Tek	
				10 - 50# Hole plug	
				1 - 5 gal. Pellets @ 65'	
				1 set 4 3/4 Drag Bits	
				2 - 5" Caps	
				2 - 5" Collars	
				3 call	

GARDEN CITY, KS      HENKLE DRILLING & SUPPLY CO., INC.      SUBLETTE, KS  
Phone 276-3278      IRRIGATION HEADQUARTERS      Phone 675-4311  
TEST HOLES \* \* \* \* \* IRRIGATION & INDUSTRIAL WELLS \* \* \* \* \* STOCK WELLS