

1 LOCATION OF WATER WELL: COUNTY: 094 STANTON	Fraction SW 1/4 NW 1/4 SE 1/4	Section Number 10	Township Number T 27 S	Range Number R 42 W
--	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?

FROM MANTER; APPX 12 1/2 MILES NORTH

2 WATER WELL OWNER: RR#, St. Address, Box # : 8673 W. HWY 160 City, State, ZIP code : MANTER, KS 67862-9501	MARTY COOK Board of Agriculture, Division of Water Resources Application Number:
---	--

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

M i l e	W	1		2		3		4	
		NW		NE					
		SW		SE					

4 DEPTH OF COMPLETED WELL 460 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.WELL'S STATIC WATER LEVEL 270 ft. below land surface measured on mo/day/yr 9/1/05
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9 7/8 in. to 460 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted

Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC	CASING JOINTS: OTHER CASING JNT- CERTILOCK
Blank casing diameter 5 in. to 460 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265	
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC	
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT	

SCREEN PERFORATED INTERVALS:	From 360 ft. to 460 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 25 ft. to 460 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE OBSERVED

Direction from well?

How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	64	BRWN SANDY CLAY			
64	75	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
75	126	01 CLAY			
126	145	04 SANDY CLAY			
145	187	05 SAND 01 CLAY			
187	213	04 SANDY CLAY 05 SAND			
213	235	05 SAND 03 SILTY CLAY			
235	270	04 SANDY CLAY 05 SAND			
270	275	07 FINE SAND 08 MEDIUM SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/27/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145	This Water Well Record was completed on (mo/day/yr) 10/06/05 by (signature)
---	---

1 LOCATION OF WATER WELL: COUNTY: 094 STANTON	Fraction 1/4 1/4 SE 1/4	Section Number 10	Township Number T 27 S	Range Number R 42 W
--	--------------------------------------	----------------------	--------------------------------	-----------------------------

2 WATER WELL OWNER: MARTY COOK RR#, St. Address, Box # : 8673 W. HWY 160 City, State, ZIP code : MANTER, KS 67862-9501	Board of Agriculture, Division of Water Resources Application Number:
--	--

FROM	TO	LITHOLOGIC LOG
275	292	07 FINE SAND
292	298	31 CALICHE 05 SAND
298	362	19 SHALE
362	384	31 CALICHE 23 SANDSTONE
384	460	31 CALICHE 23 SANDSTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/27/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 under the business name of HENKLE DRILLING & SUPPLY	This Water Well Record was completed on (mo/day/yr) 10/06/05 by (signature) <i>Brian J. Henkle</i>
--	---