

1 LOCATION OF WATER WELL: County: Sedgwick		Fraction NE 1/4 NE 1/4 NE 1/4		Section Number 27	Township Number T 28 S	Range Number R 1 EW
Distance and direction from nearest town or city street address of well if located within city? 150 Feet Southwest of 55th and Hoover Road, Wichita, Kansas						
2 WATER WELL OWNER: Vulcan Chemicals		01968023 MW-E Board of Agriculture, Division of Water Resources Application Number:				
RR#, St. Address, Box # : 6200 South Ridge Road						
City, State, ZIP Code : Wichita, Kansas 67215						
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 92 ft. ELEVATION: Approx Surface 1300				
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.				
		WELL'S STATIC WATER LEVEL 45 ft. below land surface measured on mo/day/yr 11/20/96				
		Pump test data: Well water was N/A ft. after hours pumping gpm				
		Est. Yield N/A gpm: Well water was ft. after hours pumping gpm				
		Bore Hole Diameter 8.25 in. to 93 ft. and in. to ft.				
		WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well				
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)				
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well				
		Was a chemical/bacteriological sample submitted to Department? Yes.....No..... X If yes, mo/day/yr sample was submitted				
		Water Well Disinfected? Yes.....No..... X				
5 TYPE OF BLANK CASING USED:		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued.....Clamped.....				
1 Steel 3 RMP (SR)		6 Asbestos-Cement 9 Other (specify below) Welded.....				
2 PVC 4 ABS		Stainless Steel Threaded..... X				
7 Fiberglass						
Blank casing diameter 2 in. to 77 ft. Dia. in. to ft. Dia. in. to ft.						
Casing height above land surface 36 in. weight lbs./ft. Wall thickness or gauge No. 316						
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement				
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)						
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)						
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)				
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes						
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)						
SCREEN-PERFORATED INTERVALS: From 77 ft. to 92 ft. From ft. to ft.						
GRAVEL PACK INTERVALS: From 75 ft. to 93 ft. From ft. to ft.						
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other						
Grout Intervals: From 0 ft. to 73 ft. From 73 ft. to 75 ft. From ft. to ft.						
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well				
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well						
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)						
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage						
Direction from well?		How many feet?				
FROM	TO	LITHOLOGIC LOG		FROM	TO	PLUGGING INTERVALS
0	10	Brown, Lean to Fat Clay				
10	25	Brown, Fine to Coarse Sand				
25	35	Brown Silty, Sandy Clay				
35	70	Brown, Fine to Coarse Sand				
70	85	Brown, Lean to Fat Clay				
85	92	Brown, Fine to Coarse Sand				
92		Gray Shale				
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was 1 constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 11/6/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 416 This Water Well Record was completed on (mo/day/yr) 11/6/96 under the business name of Terracon Consultants, Inc. by (signature) <i>[Signature]</i>						