

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>SEDGWICK</u>		<u>NW 1/4 SW 1/4 NE 1/4</u>	<u>33</u>	<u>T 28 S</u>	<u>R 1 E</u>
Distance and direction from nearest town or city street address of well if located within city? <u>APPROXIMATELY 4610 FT NORTH AND 1075 FT WEST OF THE SOUTHEAST CORNER OF SAID SECTION, SEDGWICK COUNTY, KANSAS</u>					
2 WATER WELL OWNER: <u>AIR PRODUCTS MANUFACTURING CORPORATION</u>		Monitoring Well No <u>2</u>			
RR#, St. Address, Box #: <u>P.O. BOX 12291</u>		Board of Agriculture, Division of Water Resources			
City, State, ZIP Code: <u>WICHITA, KANSAS 67271-2291</u>		Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: <u>105.50</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL ft. below land surface measured on mo/day/yr <u>9.12.97</u>			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter: <u>6</u> in. to <u>105.50</u> ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only <u>10 Monitoring well</u>			
		Was a chemical/bacteriological sample submitted to Department? Yes No <u>X</u> If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes <u>X</u> No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped			
1 Steel 3 RMP (SR)		Welded			
<u>2 PVC</u> 4 ABS		Threaded <u>X</u>			
Blank casing diameter <u>2</u> in. to <u>95.50</u> ft., Dia in. to ft., Dia in. to ft.					
Casing height above land surface <u>30</u> in., weight lbs./ft. Wall thickness or gauge No. <u>SC# 40</u>					
TYPE OF SCREEN OR PERFORATION MATERIAL:		10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR)		11 Other (specify)			
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS		12 None used (open hole)			
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot <u>3 Mill slot</u> 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)					
SCREEN-PERFORATED INTERVALS: From <u>105.50</u> ft. to <u>95.50</u> ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From <u>105.50</u> ft. to <u>95</u> ft., From ft. to ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout <u>3 Bentonite</u> 4 Other					
Grout Intervals: From <u>95</u> ft. to <u>75</u> ft., From <u>75</u> ft. to <u>0</u> ft., From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage <u>Chemical Plant</u>					
Direction from well? <u>EAST</u>		How many feet? <u>2000</u>			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	10	SILTY CLAY			
10	14	SILTY CLAY			
14	55	SAND & GRAVEL			
55	75	CLAY, SILT some GRAVEL			
75	91	SAND			
91	95	SILTY CLAY			
95	105.50	SAND			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>SEPT. 12, 1997</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>581</u> This Water Well Record was completed on (mo/day/yr) <u>SEPT. 26, 1997</u> under the business name of <u>LAYNE WESTERN</u> by (signature) <u>[Signature]</u>					