

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: SEDGWICK		SW 1/4 NE 1/4 SW 1/4	10	T 28 S	R 7 E
Distance and direction from nearest town or city street address of well if located within city? 6801 W. 36th S.					
2 WATER WELL OWNER: ROGER EATON					
RR#, St. Address, Box #: 1436 S. WASHINGTON					
City, State, ZIP Code: WICHITA KS 67211					
Board of Agriculture, Division of Water Resources Application Number:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 52 ft. ELEVATION:			
		Depth(s) Groundwater Encountered: 20 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL: 20 ft. below land surface measured on mo/day/yr 9-16-99			
		Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Est. Yield 25 gpm: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Bore Hole Diameter: 11 in. to 52 ft., and _____ in. to _____ ft.			
		WELL WATER TO BE USED AS:			
		☒ 5 Public water supply ☐ 8 Air conditioning ☐ 11 Injection well ☒ 6 Domestic ☐ 3 Feedlot ☐ 6 Oil field water supply ☐ 9 Dewatering ☐ 12 Other (Specify below) ☐ 2 Irrigation ☐ 4 Industrial ☒ 7 Lawn and garden only ☐ 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒ If yes, mo/day/yr sample was submitted _____			
		Water Well Disinfected? Yes ☒ No _____			
5 TYPE OF BLANK CASING USED:					
☒ 1 Steel ☐ 3 RMP (SR) ☐ 5 Wrought iron ☐ 8 Concrete tile CASING JOINTS: Glued ☒ Clamped _____ ☐ 2 PVC ☐ 4 ABS ☐ 6 Asbestos-Cement ☐ 9 Other (specify below) Welded _____ ☐ 7 Fiberglass Threaded _____					
Blank casing diameter 5 in. to 42 ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft.					
Casing height above land surface 12 in., weight 240 lbs./ft. Wall thickness or gauge No. 160psi					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
☐ 1 Steel ☐ 3 Stainless steel ☐ 5 Fiberglass ☒ 8 RMP (SR) ☐ 11 Other (specify) _____ ☐ 2 Brass ☐ 4 Galvanized steel ☐ 6 Concrete tile ☐ 9 ABS ☐ 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
☐ 1 Continuous slot ☒ 3 Mill slot ☐ 5 Gauzed wrapped ☐ 8 Saw cut ☐ 11 None (open hole) ☐ 2 Louvered shutter ☐ 4 Key punched ☐ 6 Wire wrapped ☐ 9 Drilled holes ☐ 7 Torch cut ☐ 10 Other (specify) _____					
SCREEN-PERFORATED INTERVALS: From 42 ft. to 52 ft., From _____ ft. to _____ ft.					
GRAVEL PACK INTERVALS: From 20 ft. to 52 ft., From _____ ft. to _____ ft.					
6 GROUT MATERIAL: ☒ 1 Neat cement 20 ☐ 2 Cement grout ☐ 3 Bentonite ☐ 4 Other _____					
Grout Intervals: From 3 ft. to 20 ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:					
☒ 1 Septic tank ☐ 4 Lateral lines ☐ 7 Pit privy ☐ 10 Livestock pens ☐ 14 Abandoned water well ☐ 2 Sewer lines ☐ 5 Cess pool ☐ 8 Sewage lagoon ☐ 11 Fuel storage ☐ 15 Oil well/Gas well ☐ 3 Watertight sewer lines ☐ 6 Seepage pit ☐ 9 Feedyard ☐ 12 Fertilizer storage ☐ 16 Other (specify below) ☐ 13 Insecticide storage					
Direction from well? South How many feet? 60					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	28	CLAY			
28	30	FINE SAND			
30	32	CLAY			
32	52	SAND & GRAVEL			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ (1) constructed, ☐ (2) reconstructed, or ☐ (3) plugged under my jurisdiction and was completed on (mo/day/year) 9-16-99 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 318 This Water Well Record was completed on (mo/day/yr) 9-20-99 under the business name of WENINGER DRILLING INC by (signature) Michelle Gorge					