

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number																																																																																											
County: Sedgwick		SW 1/4 SW 1/4 SW 1/4		28		T 28 S		R 1 E W																																																																																											
Distance and direction from nearest town or city street address of well if located within city?																																																																																																			
Approximately 1 3/4 miles north of Bayneville																																																																																																			
2 WATER WELL OWNER:																																																																																																			
Air Products manufacturing Corporation						Board of Agriculture, Division of Water Resources																																																																																													
RR#, St. Address, Box # : 6601 South Ridge Road						Application Number: 39,797																																																																																													
City, State, ZIP Code : Haysville, KS 67060-7134																																																																																																			
3 LOCATE WELL'S LOCATION WITH:		4 DEPTH OF COMPLETED WELL		117.10		ft. ELEVATION:		unknown																																																																																											
AN "X" IN SECTION BOX:																																																																																																			
		Depth(s) Groundwater Encountered 1 _____ ft. 2 _____ ft. 3 _____ ft. WELL'S STATIC WATER LEVEL 50 _____ ft. below land surface measured on mo/day/yr 10-17-02 Pump test data: Well water was not checked _____ ft. after _____ hours pumping _____ gpm Est. Yield unknown _____ gpm: Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter: 42 _____ in. to 117 _____ ft., and _____ in. to _____ ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒ If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes ☒ No _____																																																																																																	
5 TYPE OF BLANK CASING USED:																																																																																																			
1 Steel 2 PVC Blank casing diameter 16 _____ in. to 85 _____ ft., Dia Casing height above land surface 19 _____ in., weight 62.58 _____ lbs./ft. Wall thickness or gauge No .375		3 RMP (SR) 4 ABS 5 Wrought iron 6 Asbestos-Cement 7 Fiberglass		8 Concrete tile 9 Other (specify below) 10 Asbestos-cement 11 Other (specify) 12 None used (open hole)		CASING JOINTS: Glued _____ Clamped _____ Welded ☒ Threaded _____																																																																																													
TYPE OF SCREEN OR PERFORATION MATERIAL:																																																																																																			
1 Steel 2 Brass SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 2 Louvered shutter SCREEN-PERFORATED INTERVALS: GRAVEL PACK INTERVALS:		3 Stainless steel 4 Galvanized steel 5 Fiberglass 6 Concrete tile 7 PVC 8 RMP (SR) 9 ABS 10 Gauged wrapped 11 Wire wrapped 12 Torch cut		11 Other (specify) 12 None (open hole)		13 Saw cut 14 Drilled holes 15 Other (specify)																																																																																													
From _____ 85 _____ ft. to 115.5 _____ ft., From _____ ft. to _____ ft. From _____ 75 _____ ft. to 117 _____ ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.																																																																																																			
6 GROUT MATERIAL:																																																																																																			
1 Neat cement		2 Cement grout		3 Bentonite		4 Other		Bentonite Holeplug																																																																																											
Compacted Soil Road Sand																																																																																																			
Grout Intervals: From 0 - 5 _____ ft. to 5 - 25 _____ ft., From 25 _____ ft. to 60 _____ ft., From 60 _____ ft. to 75 _____ ft.																																																																																																			
What is the nearest source of possible contamination:																																																																																																			
1 Septic tank		4 Lateral lines		7 Pit privy		10 Livestock pens		14 Abandoned water well																																																																																											
2 Sewer lines		5 Cess pool		8 Sewage lagoon		11 Fuel storage		15 Oil well/Gas well																																																																																											
3 Watertight sewer lines		6 Seepage pit		9 Feedyard		12 Fertilizer storage		16 Other (specify below)																																																																																											
						13 Insecticide storage		None known																																																																																											
Direction from well? _____ How many feet? _____																																																																																																			
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr><td>0</td><td>2</td><td>Topsoil</td><td></td><td></td><td></td></tr> <tr><td>2</td><td>15</td><td>Clay, brown</td><td></td><td></td><td></td></tr> <tr><td>15</td><td>33</td><td>Sand and gravel, fine, medium, some coarse</td><td></td><td></td><td></td></tr> <tr><td>33</td><td>40</td><td>Clay, brown</td><td></td><td></td><td></td></tr> <tr><td>40</td><td>52</td><td>Clay, tan</td><td></td><td></td><td></td></tr> <tr><td>52</td><td>60</td><td>Sand and gravel, fine, medium with clay</td><td></td><td></td><td></td></tr> <tr><td>60</td><td>65</td><td>Sand and gravel, fine, medium</td><td></td><td></td><td></td></tr> <tr><td>65</td><td>70</td><td>Clay, tan</td><td></td><td></td><td></td></tr> <tr><td>70</td><td>86</td><td>Clay, gray and tan</td><td></td><td></td><td></td></tr> <tr><td>86</td><td>104</td><td>Sand, very fine, fine, medium</td><td></td><td></td><td></td></tr> <tr><td>104</td><td>105.5</td><td>Sand and gravel, fine, medium</td><td></td><td></td><td></td></tr> <tr><td>105.5</td><td>114</td><td>Sand, very fine, fine, medium</td><td></td><td></td><td></td></tr> <tr><td>114</td><td>115.5</td><td>Sand and gravel, fine, medium</td><td></td><td></td><td></td></tr> <tr><td>115.5</td><td>117</td><td>Clay</td><td></td><td></td><td></td></tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	0	2	Topsoil				2	15	Clay, brown				15	33	Sand and gravel, fine, medium, some coarse				33	40	Clay, brown				40	52	Clay, tan				52	60	Sand and gravel, fine, medium with clay				60	65	Sand and gravel, fine, medium				65	70	Clay, tan				70	86	Clay, gray and tan				86	104	Sand, very fine, fine, medium				104	105.5	Sand and gravel, fine, medium				105.5	114	Sand, very fine, fine, medium				114	115.5	Sand and gravel, fine, medium				115.5	117	Clay			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS																																																																																														
0	2	Topsoil																																																																																																	
2	15	Clay, brown																																																																																																	
15	33	Sand and gravel, fine, medium, some coarse																																																																																																	
33	40	Clay, brown																																																																																																	
40	52	Clay, tan																																																																																																	
52	60	Sand and gravel, fine, medium with clay																																																																																																	
60	65	Sand and gravel, fine, medium																																																																																																	
65	70	Clay, tan																																																																																																	
70	86	Clay, gray and tan																																																																																																	
86	104	Sand, very fine, fine, medium																																																																																																	
104	105.5	Sand and gravel, fine, medium																																																																																																	
105.5	114	Sand, very fine, fine, medium																																																																																																	
114	115.5	Sand and gravel, fine, medium																																																																																																	
115.5	117	Clay																																																																																																	
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:																																																																																																			
This water well was (1) constructed , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 10-17-02 and this record is true to the best of my knowledge and belief. Kansas																																																																																																			
Water Well Contractor's License No 185 This Water Well Record was completed on (mo/day/yr) 10-24-02																																																																																																			
under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment, Inc.</i>																																																																																																			
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone 785-296-5524. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.																																																																																																			