

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Sedgwick	FRACTION SW 1/4 NW 1/4 SE 1/4	SECTION NUMBER 7	TOWNSHIP NUMBER T 28 S	RANGE NUMBER R 1W E/W
---	--	-----------------------------------	---	--

Distance and direction from nearest town or city street address of well if located within city?
11000 SW Blvd. Schulte, Kansas

2 WATER WELL OWNER: ST. PETER THE APOSTLE SCHOOL RR#, ST. ADDRESS, BOX #: 11000 SW Blvd. CITY, STATE: Schulte, Kansas	ZIP CODE: 	Application Number: PWS#U7310 Board of Agriculture, Division of Water Resource
--	--------------------------	--

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL: **110** ft. **ELEVATION:** **KDHE PROJECT # PW 002323** ft.
 Depth of groundwater Encountered: _____ ft.
WELL'S STATIC WATER LEVEL **30.5** FT. BELOW LAND SURFACE MEASURED ON **11/25/03** mo/day/yr.
 Pump test data: Well water was _____ ft. after _____ hours of pumping @ _____ gpm
 Est. Yield: _____ gpm Well water was _____ ft. after _____ hours of pumping @ _____ gpm
 Bore Hole Diameter **15** in. to **110** ft. and _____ in. to _____ ft.
WELL WATER TO BE USED AS:
 1. Domestic 3. Feedlot **5. Public water supply** 7. Lawn and garden only 9. Dewatering 11. Injection well
 2. Irrigation 4. Industrial 6. Oil field water supply 8. Air conditioning 10. Monitoring well 12. Other (Specify below)
 Was a chemical/bacteriological sample submitted to Department? **YES** **NO** ; If yes, what mo/day/yr was sample submitted
 Was Water Well Disinfected? **YES** **NO**

5 TYPE OF CASING USED:
 1. Steel 3. RPM (SR) 5. Wrought Iron 7. Fiberglass 9. Other (Specify below)
2. PVC 4. ABS 6. Asbestos-Cement 8. Concrete tile
 Blank casing diameter **6** in. to **105** ft., Dia. _____ in. to _____ ft., Dia. _____ in. to _____ ft.
 Casing height above land surface: **12** in., Weight: **3.680** lbs. / ft. Wall thickness or gauge No. **SCHED. 40 .280**
TYPE OF SCREEN OR PERFORATION MATERIAL:
 1. Steel 3. Stainless Steel 5. Fiberglass **7. PVC** 9. ABS 11. Other (specify)
 2. Brass 4. Galvanized 6. Concrete Tile 8. RMP (SR) 10. Asbestos-Cement 12. None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:
 1. Continuous slot 3. Mill slot 5. Gauzed wrapped 7. Torch cut 9. Drilled holes 11. None (open hole)
 2. Louvered shutter 4. Key punched 6. Wire wrapped **8. Saw cut** 10. Other (specify)
SCREEN - PERFORATION INTERVAL From **95** ft. to **110** ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft.
GRAVEL PACK INTERVALS: From **27** ft. to **35** ft., From **40** ft. to **85** ft., From **95** ft. to **110** ft., From _____ ft. to _____ ft.

6 GROUT MATERIALS: 1. Neat cement 2. Cement Grout 3. Bentonite Other
 Grout Intervals: From _____ ft. to _____ ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft.
 What is the nearest source of possible contamination:
 1. Septic tank 4. Lateral lines 7. Pit privy 10. Livestock pens 13. Insecticide storage 15. Oil well/Gas well
 2. Sewer lines 5. Cess Pool **8. Sewage lagoon** 11. Fuel storage 14. Abandon water well 16. Other (specify below)
 3. Watertight sewer line 6. Seepage pit 9. Feed yard 12. Fertilizer storage
 Direction from well? **Northeast** How many feet? **300**

From	To	LITHOLOGIC LOG	From	To		
0	4	topsoil			GROUTING INTERVALS	
4	18	clay	4	24		cement grout
18	35	medium sand	24	27		bentonite hole plug
35	97	clay	27	35		gravel pack
97	110	medium fine sand	35	40		bentonite hole plug
110	115	shale	40	85		gravel pack
			85	95		bentonite hole plug
			95	110		gravel pack

7 Contractor's or Landowner's Certification: This water well was 1. constructed 2. reconstructed or 3. plugged under my jurisdiction and was completed on (mo/day/year) 11/25/2003 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This water well record was completed on (mo/day/year) 11/28/2003 under the business name of Harp Well & Pump Service Inc. by (signature) <i>Jo d d S. Harp</i>
--