

1 LOCATION OF WATER WELL: Sedgwick		FRACTION NE 1/4 SE 1/4 NE 1/4	SECTION NUMBER 15	TOWNSHIP NUMBER T 28 S	RANGE NUMBER R 1W E/W
Distance and direction from nearest town or city street address of well if located within city? 4240 S. Gilda Wichita, Kansas					
2	WATER WELL OWNER: DINH, Alan RR#,ST. ADDRESS,BOX #: 4240 S. Gilda CITY, STATE: Wichita, Kansas		Board of Agriculture, Division of Water Resource ZIP CODE: Application Number:		
3	LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: 65 ft. ELEVATION:		
		Depth of groundwater Encountered: ft.			
		WELL'S STATIC WATER LEVEL 40 FT. BELOW LAND SURFACE MEASURED ON mo/day/yr: 9/7/04			
		Pump test data: Well water was ft. after hours of pumping @ gpm			
		Est. Yield: gpm Well water was ft. after hours of pumping @ gpm			
		Bore Hole Diameter 12 in. to 65 ft. and in. to ft.			
		WELL WATER TO BE USED AS:			
		☐ 1. Domestic ☐ 3. Feedlot ☐ 5. Public water supply ☒ 7. Lawn and garden only ☐ 9. Dewatering ☐ 11. Injection well ☐ 2. Irrigation ☐ 4. Industrial ☐ 6. Oil field water supply ☐ 8. Air conditioning ☐ 10. Monitoring well ☐ 12. Other (Specify below)			
		Was a chemical/bacteriological sample submitted to Department? YES ☒ NO ; If yes, what mo/day/yr was sample submitted Was Water Well Disinfected? ☒ YES NO			
5	TYPE OF CASING USED:				
☐ 1. Steel ☐ 3. RPM (SR) ☐ 5. Wrought Iron ☐ 7. Fiberglass ☐ 9. Other (Specify below) CASING JOINTS: ☒ Glued Threaded ☒ 2. PVC ☐ 4. ABS ☐ 6. Asbestos-Cement ☐ 8. Concrete tile SDR-26 Welded Clamped					
Blank casing diameter 5 in. to 45 ft., Dia. in. to ft., Dia. in. to ft.					
Casing height above land surface: 16 in., Weight: 2.35 lbs. / ft. Wall thickness or gauge No. .214					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
☐ 1. Steel ☐ 3. Stainless Steel ☐ 5. Fiberglass ☒ 7. PVC ☐ 9. ABS ☐ 11. Other (specify) ☐ 2. Brass ☐ 4. Galvanized ☐ 6. Concrete Tile ☐ 8. RMP (SR) ☐ 10. Asbestos-Cement ☐ 12. None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
☐ 1. Continuous slot ☐ 3. Mill slot ☐ 5. Gauzed wrapped ☐ 7. Torch cut ☐ 9. Drilled holes ☐ 11. None (open hole) ☐ 2. Louvered shutter ☐ 4. Key punched ☐ 6. Wire wrapped ☒ 8. Saw cut ☐ 10. Other (specify)					
SCREEN - PERFORATION INTERVAL From 45 ft. to 65 ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 24 ft. to 65 ft., From ft. to ft.					
6	GROUT MATERIALS: 1. Neat cement 2. Cement Grout 3. Bentonite Other bentonite hole plug				
Grout Intervals: From 4 ft. to 24 ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:					
☐ 1. Septic tank ☐ 4. Lateral lines ☐ 7. Pit privy ☐ 10. Livestock pens ☐ 13. Insecticide storage ☐ 15. Oil well/Gas well ☐ 2. Sewer lines ☐ 5. Cess Pool ☐ 8. Sewage lagoon ☐ 11. Fuel storage ☐ 14. Abandon water well ☐ 16. Other (specify below) ☒ 3. Watertight sewer line ☐ 6. Seepage pit ☐ 9. Feed yard ☐ 12. Fertilizer storage					
Direction from well? West How many feet? 15					
LITHOLOGIC LOG					
From	To				
0	4	topsoil			
4	30	sandy clay			
30	38	sand			
38	45	clay			
45	65	sand			
RECEIVED					
OCT 04 2004					
BUREAU OF WATER					
7	Contractor's or Landowner's Certification: This water well was ☒ constructed ☐ reconstructed or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 9/7/2004 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This water well record was completed on (mo/day/year) 9/10/2004 under the business name of Harp Well & Pump Service Inc. by (signature) <i>Jedd S. Harp</i>				