


WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: <u>Sedgwick</u> Fraction <u>NE 1/4 NW 1/4 SE 1/4</u> 1/4 Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☒		Section Number <u>7</u> Township No. <u>T 28 S</u> Range Number <u>R 1</u> ☐ E ☒ W																																																																					
2 WATER WELL OWNER: RR#, Street Address, Box #: <u>Carl Hall</u> City, State, ZIP Code: <u>110246 Hollywood eb. Wichita, KS 67215</u>		Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																					
3 LOCATE WELL WITH AN "X" IN SECTION BOX:  S -----1 mile-----	4 DEPTH OF COMPLETED WELL <u>52</u> ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL..... <u>22</u>ft. below land surface measured on mo/day/yr. <u>2-19-11</u> Pump test data: Well water wasft. after hours pumping gpm EST. YIELD <u>25</u> gpm. Well water wasft. after hours pumping gpm Bore Hole Diameter ... <u>10.5</u> in. to ... <u>52</u>ft., andin. toft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☒ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted Water well disinfected? ☒ Yes ☐ No																																																																						
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter <u>5</u> in. to ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface..... <u>12</u> in., Weight <u>27</u>lbs./ft., Wall thickness or gauge No. <u>5-1480</u> TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From... <u>38</u> ft. to ... <u>52</u> ft., From ft. to ft. From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From... <u>22</u> ft. to ... <u>52</u> ft., From ft. to ft. From ft. to ft., From ft. to ft.																																																																							
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From... <u>3</u> ft. to ... <u>23</u> ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☒ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well ... <u>North</u> Distance from well ... <u>12'</u>																																																																							
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> </tr> </thead> <tbody> <tr><td>0</td><td>3</td><td>Top Soil</td></tr> <tr><td>3</td><td>12</td><td>Gray Clay</td></tr> <tr><td>12</td><td>22</td><td>Brown Clay</td></tr> <tr><td>22</td><td>35</td><td>fine sand</td></tr> <tr><td>35</td><td>48</td><td>med sand</td></tr> <tr><td>48</td><td>52</td><td>Brown Clay</td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>	FROM	TO	LITHOLOGIC LOG	0	3	Top Soil	3	12	Gray Clay	12	22	Brown Clay	22	35	fine sand	35	48	med sand	48	52	Brown Clay																<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>		FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																														
FROM	TO	LITHOLOGIC LOG																																																																					
0	3	Top Soil																																																																					
3	12	Gray Clay																																																																					
12	22	Brown Clay																																																																					
22	35	fine sand																																																																					
35	48	med sand																																																																					
48	52	Brown Clay																																																																					
FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																					
00001287																																																																							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) <u>2-19-11</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>740</u> This Water Well Record was completed on (mo/day/year) under the business name of <u>Whitinger Drilling Inc.</u> by (signature) <u>[Signature]</u>																																																																							
INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY and PRINT</u> clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																							