

Drilling Log

Project Name Cessna						Boring No. WC-2	
Project No. 85-141-4-002						Page 1 of 2	
Ground Elevation 1304.6			Location			Total Footage	
Drilling Type	Hole Size	Overburden Footage	Bedrock Footage	No. of Samples	No. Core Boxes	Depth To Water	Date Measured
Rotary Wash	6"	15'	0	2	0	See Remarks	
Drilling Co. Layne-Western Company Inc				Driller (s) J Von Holt J. Watkins			
Drilling Rig. Gardner Denver 500				Type of Penetration Test Standard			
Date			To		Field Observer (s) M Eversman		

Depth	Description	Class.	Blow Count	Recov.	Sample or Box No.	Remarks
1						
2						
3						
4	Brown, silty clay med to high plasticity					
5						
6						
7						
8	Brown Silty clay moist med to high plasticity, v. shft, contains some roots		8-11-12		SS₁	
9						
10						
11						
12						
13	Grey Silty Clay, moist, med to high plasticity, shft		4-4-6		SS₂	

Drilling Log, continued

Project Name <u>Cessna</u>						Boring No. <u>WC-2</u>
Project No. <u>85-141-4-002</u>						Page <u>1</u> of <u>2</u>
						Date <u>3/15/86</u>
Depth	Description	Log or Class	Blow Count	Core Recov. & Loss	Box or Sample No.	Remarks
15	TD = 15.0'				SS ₂	Set 2" PVC at 15.0', 5'screen Gravel Pack 15.0' - 9.0' Bentonite Seal 9.0' - 7.0' Grouted to Surface and installed lock base Completed @ 6:00 pm

