

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: <u>Sedgewick</u> Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☒		Fraction <u>1/4 NW 1/4 SE 1/4 SE 1/4</u> Section Number <u>7</u> Township No. <u>T 28 S</u> Range Number <u>R 1 E</u> ☒ <u>W</u>																																																
2 WATER WELL OWNER: <u>Mike Schumacher</u> RR#, Street Address, Box #: <u>10702 W. 35th S</u> City, State, ZIP Code: <u>Wichita, KS</u>		Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N <table border="1" style="width: 100%; text-align: center; border-collapse: collapse;"> <tr> <td style="width: 25%;">NW</td> <td style="width: 25%;">NE</td> </tr> <tr> <td style="width: 25%;">SW</td> <td style="width: 25%;">SE</td> </tr> </table> S -----1 mile-----	NW	NE	SW	SE	4 DEPTH OF COMPLETED WELL <u>60</u> ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL <u>24</u> ft. below land surface measured on mo/day/yr..... Pump test data: Well water was..... ft. after..... hours pumping..... gpm EST. YIELD..... gpm. Well water was..... ft. after..... hours pumping..... gpm Bore Hole Diameter <u>1.2</u> in. to ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☐ Irrigation ☐ Industrial ☒ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted..... Water well disinfected? ☒ Yes ☐ No																																													
NW	NE																																																	
SW	SE																																																	
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter <u>5</u> in. to <u>60</u> ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface <u>16</u> in., Weight <u>1600</u> lbs./ft., Wall thickness or gauge No. <u>26</u> TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From <u>40</u> ft. to <u>60</u> ft., From ft. to ft. From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From <u>24</u> ft. to <u>60</u> ft., From ft. to ft. From ft. to ft., From ft. to ft.																																																		
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From <u>4</u> ft. to <u>24</u> ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☒ Watertight sewer lines ☐ Sewage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well <u>East</u> Distance from well <u>75'</u>																																																		
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>2</td> <td>Top Soil</td> </tr> <tr> <td>2</td> <td>26</td> <td>Clay</td> </tr> <tr> <td>26</td> <td>31</td> <td>fine Sand</td> </tr> <tr> <td>31</td> <td>33</td> <td>med Sand</td> </tr> <tr> <td>33</td> <td>60</td> <td>Clay</td> </tr> </tbody> </table>	FROM	TO	LITHOLOGIC LOG	0	2	Top Soil	2	26	Clay	26	31	fine Sand	31	33	med Sand	33	60	Clay	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>		FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																											
FROM	TO	LITHOLOGIC LOG																																																
0	2	Top Soil																																																
2	26	Clay																																																
26	31	fine Sand																																																
31	33	med Sand																																																
33	60	Clay																																																
FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) <u>11/16/12</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>6611</u> This Water Well Record was completed on (mo/day/year) <u>11/29/30</u> under the business name of <u>Chase Drilling</u> by (signature) <u>[Signature]</u> INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each <u>constructed</u> well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																		