

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction NE 1/4 SW/4 SW 1/4	Section number 8	Township number T 28 S R 1	Range number 1								
2. Distance and direction from nearest town or city: of Schulte, Ks. Street address of well location if in city:			3. Owner of well: Mid Continent Indust. Park P. O. Box 12086 Wichita, Ks. 67277 City, state, zip code:										
4. Locate with "X" in section below: N 1 Mile W <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td>NW</td><td>NE</td></tr><tr><td>SW</td><td>SE</td></tr></table> E S 1 Mile			NW	NE	SW	SE	Sketch map: N 1 Mile W <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td>NW</td><td>NE</td></tr><tr><td>SW</td><td>SE</td></tr></table> E S 1 Mile			NW	NE	SW	SE
NW	NE												
SW	SE												
NW	NE												
SW	SE												
5. Type and color of material			From	To	6. Bore hole dia. 30 in. Completion date 11/27/79 Well depth 100 ft.								
Top soil			0	5	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary								
Clay			5	10	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☒ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other								
Sandy clay			10	15	☒ Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 72 in. RMP ☐ PVC ☐ Weight 25 lbs./ft. Dia. 8 in. to 85 ft. depth ☒ All thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 277								
Med. sand & gravel			15	25	☒ Screen: Manufacturer's name Mustang Type wire wrap Dia. 8" Slot/gauze .060 Length 15' Set between 85 ft. and 100 ft. Gravel pack? yes Size range of material 1/8-1/4"								
Med. sand & gravel & clay			25	30	11. Static water level: 22 ft. below land surface Date 11/20/79 mo./day/yr.								
Fine sand			30	35	12. Pumping level below land surfaces: 65 ft. after 4 hrs. pumping 150 g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 180 g.p.m.								
Med. sand & gravel			35	40	13. Water sample submitted: ☐ Yes ☒ No Date ☐								
Gray clay			40	60	14. Well head completion: ☒ Pitless adapter 18 inches above grade								
Blue clay			60	75	15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 7 ft. to 27 ft.								
Gray clay			75	85	16. Nearest source of possible contamination: ft. 1200 Direction SE Type Sewer Well disinfected upon completion? ☒ Yes ☐ No								
Med. sand & gravel			85	100	17. Pump: ☐ Not installed Manufacturer's name Layne & Bowler Model number 6RKLC HP 10 Volts 460 Length of drop pipe 83 ft. capacity 160 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other								
(Use a second sheet if needed)													
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name License No. Address Wichita, Kansas Signed Dennis Appleby Date 12-18-79 Authorized representative										
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley													

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5