


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction SE 1/4 SW 1/4 SE 1/4	Section number 3	Township number T 28 S R 1	Range number 1
2. Distance and direction from nearest town or city: SW Edge of Wichita on K42 Highway Street address of well location if in city:			3. Owner of well: Cessna Prospect Plant R.R. or street: Wichita, Kansas City, state, zip code:			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 30 in. Completion date 11/30/79 Well depth 72 ft.		
		Well No. 4		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☐ Public supply ☒ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Top soil		0	5	9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 36 in. RMP ☐ PVC ☐ Weight 34.24 lbs./ft. Dia. 10 in. to 60 ft. depth Wall thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. .307		
Sandy clay		5	10	10. Screen: Manufacturer's name Mustang Type S.S. Wire Wrap 10" Slot/gauze .080 Length 15' Set between 62 ft. and 72 ft. 45 ft. and 50 ft.		
Clay		10	15	Gravel pack? yes Size range of material 1/2 x 1/2		
Sandy clay		15	23	11. Static water level: 26 ft. below land surface Date 11/30/79		
Fine to med. sand & gravel		23	27	12. Pumping level below land surfaces: 32 ft. after 2 hrs. pumping 250 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 500 g.p.m.		
Med. to coarse sand & gravel		27	50	13. Water sample submitted: ☐ Yes ☒ No Date		
Red clay		50	55	14. Well head completion: ☐ Pitless adapter 36 inches above grade		
Gray clay		55	60	15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 20 ft. to 0 ft.		
Med. sand & gravel		60	72	16. Nearest source of possible contamination: Cast Iron Sewer Line ft. 60 Direction West Type Sewer Line Well disinfected upon completion? ☒ Yes ☐ No		
(Use a second sheet if needed)				17. Pump: ☐ Not installed Manufacturer's name Layne Model number BRKMC HP 15 Volts 460 Length of drop pipe 50 ft. capacity 250 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name Wichita, Kansas License No. Address Wichita, Kansas Signed [Signature] Date 12/4/79 Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5