

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Sedgwick	SE 1/4 S 1/2 SE 1/4	3	T 28 S	R 1 E W

Distance and direction from nearest town or city, street address of well if located within city?

(as below)

2 WATER WELL OWNER:	Cessna Aircraft	Well No. 1
RR#, St. Address, Box # :	Wallace Division	Board of Agriculture, Division of Water Resources
City, State, ZIP Code :	Wichita, Ks.	Application Number: 38411

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 17' ft. ELEVATION:
	Depth(s) Groundwater Encountered 19' 6" ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 19' 6" ft. below land surface measured on mo/day/yr 1/28/87 Pump test data: Well water was 251.2" ft. after 2 1/2 hours pumping 300 gpm Est. Yield 300 gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 33 in. to 45' ft., and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes ☒ No

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 PVC	4 ABS	7 Fiberglass	Welded ☒
Blank casing diameter 10 in. to 29' 10" ft., Dia.			Threaded
Casing height above land surface 2' in., weight 40.48 lbs.			Wall thickness or gauge No. 365
TYPE OF SCREEN OR PERFORATION MATERIAL:	7 PVC	10 Asbestos-cement	
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 Drilled holes
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify)
SCREEN-PERFORATED INTERVALS:	From 31' 10" ft. to 47' ft.		
	From 16' ft. to 47' ft.		
GRAVEL PACK INTERVALS:	From 16' ft. to 47' ft.		

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
GROUT INTERVALS:	From 6' BGL ft. to 16' BGL ft.			
What is the nearest source of possible contamination:	1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens
	2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage
	3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage
Direction from well? South				13 Insecticide storage
				14 Abandoned water well
				15 Oil well/Gas well
				16 Other (specify below)
				20' bar ditch
				How many feet? 20-25'

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	6"	Black top			
6"	12'	Red-brown clay			
12	21	xxxxxxx Med. sand & Gravel			
21	22	Gray clay			
22	26	Med. sand & gravel			
26	28	Gray clay			
28	46	Med sand and gravel			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 3/6/87 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 102 This Water Well Record was completed on (mo/day/yr) 1/1/87 under the business name of Layne-Western Co., Inc., Wichita, Ks by (signature) Joe Johnson
--

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Office of Oil Field and Environmental Geology, Regulation and Permitting Section, Topeka, Kansas 66620-7500, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.

1810000098-21