

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	☒ Fraction NW 1/4 NW 1/4 SW 1/4	Section number 7	Township number T 28 S	Range number R 1W E 1W																																																									
☒ Distance and direction from nearest town or city: 3650 S. 119th West Street address of well location if in city:			3. Owner of well: Bob Gillette R.R. or street: 3650 S. 119th West City, state, zip code: Goddard, Kansas																																																												
4. Locate with "X" in section below: SCHULTE, KANSAS 			6. Bore hole dia. <u>11</u> in. Completion date <u>2-9-79</u> Well depth <u>120</u> ft.																																																												
5. Type and color of material <table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th>From</th> <th>To</th> </tr> </thead> <tbody> <tr><td>Topsoil</td><td>0</td><td>3</td></tr> <tr><td>Clay</td><td>3</td><td>25</td></tr> <tr><td>Fine sand</td><td>25</td><td>50</td></tr> <tr><td>Clay</td><td>50</td><td>70</td></tr> <tr><td>Fine sand with clay balls</td><td>70</td><td>82</td></tr> <tr><td>Clay</td><td>82</td><td>90</td></tr> <tr><td>Fine sand</td><td>90</td><td>98</td></tr> <tr><td>Clay</td><td>98</td><td>103</td></tr> <tr><td>Fine sand</td><td>103</td><td>120</td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>				From	To	Topsoil	0	3	Clay	3	25	Fine sand	25	50	Clay	50	70	Fine sand with clay balls	70	82	Clay	82	90	Fine sand	90	98	Clay	98	103	Fine sand	103	120																												7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary			
				From	To																																																										
			Topsoil	0	3																																																										
			Clay	3	25																																																										
			Fine sand	25	50																																																										
Clay	50	70																																																													
Fine sand with clay balls	70	82																																																													
Clay	82	90																																																													
Fine sand	90	98																																																													
Clay	98	103																																																													
Fine sand	103	120																																																													
8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other																																																															
9. Casing: Material <u>Styrene</u> Height: Above or below <u>1111</u> Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☒ PVC ☐ Weight <u> </u> lbs./ft. Dia. <u>5</u> in. to <u>120</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>200</u>																																																															
10. Screen: Manufacturer's name <u>Sunflower plastic</u> Type <u>styrene</u> Dia. <u>5"</u> Slot/gauge <u>.06</u> Length <u>30'</u> Set between <u>90</u> ft. and <u>120</u> ft. <u> </u> ft. and <u> </u> ft. Gravel pack? ☒ yes Size range of material <u>1-1/8"</u>																																																															
11. Static water level: <u>20</u> ft. below land surface Date <u>2-9-79</u> mo./day/yr.																																																															
12. Pumping level below land surfaces: <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m.																																																															
☒ Water sample submitted: <u> </u> mo./day/yr. <u> </u> Yes ☒ No Date <u> </u>																																																															
14. Well head completion: ☒ Pitless adapter <u>12</u> inches above grade																																																															
15. Well grouted? ☒ yes <u>1-2 fine sand mix</u> With: <u> </u> Neat cement <u> </u> Bentonite ☒ Concrete Depth: From <u>40"</u> ft. to <u>14</u> ft.																																																															
16. Nearest source of possible contamination: ft. <u>150</u> Direction <u>East</u> Type <u>Lagoon</u> Well disinfected upon completion? ☒ Yes ☐ No																																																															
17. Pump: Manufacturer's name <u>Jacuzzi</u> Model number <u>7S4C</u> HP <u>3/4</u> Volts <u>230</u> Length of drop pipe <u>75</u> ft. capacity <u>20</u> g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																																																															
(Use a second sheet if needed)																																																															
18. Elevation:		19. Remarks:		20. Water well contractor's certification:																																																											
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley		Flat ground		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name <u>Wichita, Kansas</u> License No. <u>67209</u> Address <u> </u> Signed <u>M. Arnold</u> Date <u>3-3-79</u> Authorized representative																																																											

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5