

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County SEDGWICK	Fraction NW SW 1/4 1/4 1/4	Section number 8	Township number 28 T S R	Range number 1W E/W
2. Distance and direction from nearest town or city: Street address of well location if in city: more than 1/2 mile North		3. Owner of well: Wichita Trane Air Conditioning Co. R.R. or street: 220 South Washington City, state, zip code: Wichita, Kansas			
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: of McArthur Road, Schulte, Kansas			
5. Type and color of material		From	To	6. Bore hole dia. 11 in. Completion date 3-28-79 Well depth 45 ft.	
Topsoil		0	3	7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Clay		3	15	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Fine Sand		15	23	9. Casing: Material styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight 12 lbs./ft. Dia. 5 in. to 45 ft. depth Wall Thickness: inches or Dia. 5 in. to 45 ft. depth Gauge No. .200	
Medium Sand		23	43	10. Screen: Manufacturer's name Sunflower Plastic Type styrene Dia. 5" Slot/gauge 1/4" .06 Length 20' Set between 25 ft. and 45 ft. Gravel pack? ☒ yes Size range of material 1/4-1/8"	
				11. Static water level: 20 ft. below land surface Date 3-28-79 mo./day/yr.	
				12. Pumping level below land surfaces: ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.	
				13. Water sample submitted: ☒ Yes ☐ No Date well seal mo./day/yr.	
				14. Well head completion: 12 inches above grade ☐ Pitless adapter	
				15. Well grouted? yes 1-2 fine sand mix With: ☒ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.	
				16. Nearest source of possible contamination: NONE ft. ____ Direction ____ Type ____ Well disinfected upon completion? ☒ Yes ☐ No	
				17. Pump: ☐ Not installed Manufacturer's name Sta-Rite Model number 40 Series HP 2 Volts 230 Length of drop pipe 31 ft. capacity 35 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
18. Elevation:		19. Remarks: Flat Ground Septic system not installed at this time. No apparent source for contamination.			
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas Signed M. Arnold Date 3-19-79 Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5