

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number																																																																																											
County: Sedgwick		SW ¼ NE ¼ NE ¼		10		T 28 S		R 1 E/W																																																																																											
Distance and direction from nearest town or city street address of well if located within city? Approc. 3/4 mi. north and 3/4 mi. west of Oatville, KS																																																																																																			
2 WATER WELL OWNER: Cessna Aircraft Co., Environmental Resources																																																																																																			
RR#, St. Address, Box # :				P.O. Box 7704			Board of Agriculture, Division of Water Resources																																																																																												
City, State, ZIP Code :				Wichita, Kansas 67277			Application Number: n/a																																																																																												
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:			4 DEPTH OF COMPLETED WELL: 89 ft. ELEVATION: unknown																																																																																																
			Depth(s) Groundwater Encountered 1. 18.5 ft. 2. ft. 3. ft.																																																																																																
			WELL'S STATIC WATER LEVEL 18.5 ft. below land surface measured on mo/day/yr 6/28/88																																																																																																
			Pump test data: Well water was not ck'd ft. after hours pumping gpm																																																																																																
			Est. Yield 100 gpm: Well water was ft. after hours pumping gpm																																																																																																
			Bore Hole Diameter 36 in. to 86 ft. and in. to ft.																																																																																																
			WELL WATER TO BE USED AS:																																																																																																
			5 Public water supply		8 Air conditioning		11 Injection well																																																																																												
			1 Domestic		3 Feedlot		6 Oil field water supply		9 Dewatering																																																																																										
			2 Irrigation		4 Industrial		7 Lawn and garden only		10 Observation well																																																																																										
									12 Other (Specify below)																																																																																										
									CONTAINMENT																																																																																										
Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted																																																																																																			
Water Well Disinfected? Yes No ☒																																																																																																			
5 TYPE OF BLANK CASING USED:																																																																																																			
1 Steel			3 RMP (SR)			5 Wrought iron			8 Concrete tile																																																																																										
2 PVC			4 ABS			6 Asbestos-Cement			9 Other (specify below)																																																																																										
						7 Fiberglass			CASING JOINTS: Glued Clamped																																																																																										
									Welded ☒ Threaded																																																																																										
Blank casing diameter 12 3/4 in. to 35 ft. Dia 12 3/4 in. to 76 ft. Dia in. to ft.																																																																																																			
Casing height above land surface 36 in. weight 49.56 lbs./ft. Wall thickness or gauge No. 375																																																																																																			
TYPE OF SCREEN OR PERFORATION MATERIAL:																																																																																																			
1 Steel			3 Stainless steel			5 Fiberglass			7 PVC																																																																																										
2 Brass			4 Galvanized steel			6 Concrete tile			8 RMP (SR)																																																																																										
									10 Asbestos-cement																																																																																										
									11 Other (specify)																																																																																										
									12 None used (open hole)																																																																																										
SCREEN OR PERFORATION OPENINGS ARE:																																																																																																			
1 Continuous slot			3 Mill slot			5 Gauzed wrapped			8 Saw cut																																																																																										
2 Louvered shutter			4 Key punched			6 Wire wrapped			9 Drilled holes																																																																																										
						7 Torch cut			10 Other (specify)																																																																																										
SCREEN-PERFORATED INTERVALS:																																																																																																			
From 090 slot 35 ft. to 44 ft.			From 040 " 76 ft. to 86 ft.			From 25 ft. to 47 ft.			From 50 ft. to 86 ft.																																																																																										
GRAVEL PACK INTERVALS:																																																																																																			
From 25 ft. to 47 ft.			From 50 ft. to 86 ft.																																																																																																
6 GROUT MATERIAL:																																																																																																			
a) Neat cement			2 Cement grout			b) 3 Bentonite			4 Other																																																																																										
Grout Intervals: From 5 ft. to 25 ft. From 47 ft. to 50 ft. From ft. to ft.																																																																																																			
What is the nearest source of possible contamination:																																																																																																			
1 Septic tank			4 Lateral lines			7 Pit privy			10 Livestock pens																																																																																										
2 Sewer lines			5 Cess pool			8 Sewage lagoon			11 Fuel storage																																																																																										
3 Watertight sewer lines			6 Seepage pit			9 Feedyard			12 Fertilizer storage																																																																																										
									13 Insecticide storage																																																																																										
									14 Abandoned water well																																																																																										
									15 Oil well/Gas well																																																																																										
									16 Other (specify below)																																																																																										
									no known source																																																																																										
Direction from well? How many feet?																																																																																																			
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>29</td> <td>Topsoil & clay, brown & green</td> <td></td> <td></td> <td></td> </tr> <tr> <td>29</td> <td>43</td> <td>Sand & gravel, fine to very fine to medium</td> <td></td> <td></td> <td></td> </tr> <tr> <td>43</td> <td>52</td> <td>Clay, yellow - tan</td> <td></td> <td></td> <td></td> </tr> <tr> <td>52</td> <td>69</td> <td>Sand & gravel, very fine to fine</td> <td></td> <td></td> <td></td> </tr> <tr> <td>69</td> <td>69.5</td> <td>Clay, tan - hard</td> <td></td> <td></td> <td></td> </tr> <tr> <td>69.5</td> <td>75</td> <td>Sand & gravel, very fine to fine w/thin clay streak @ 72'</td> <td></td> <td></td> <td></td> </tr> <tr> <td>75</td> <td>76</td> <td>Clay, tan</td> <td></td> <td></td> <td></td> </tr> <tr> <td>76</td> <td>86</td> <td>Sand & gravel, fine to very fine</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG	0	29	Topsoil & clay, brown & green				29	43	Sand & gravel, fine to very fine to medium				43	52	Clay, yellow - tan				52	69	Sand & gravel, very fine to fine				69	69.5	Clay, tan - hard				69.5	75	Sand & gravel, very fine to fine w/thin clay streak @ 72'				75	76	Clay, tan				76	86	Sand & gravel, fine to very fine																																							
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG																																																																																														
0	29	Topsoil & clay, brown & green																																																																																																	
29	43	Sand & gravel, fine to very fine to medium																																																																																																	
43	52	Clay, yellow - tan																																																																																																	
52	69	Sand & gravel, very fine to fine																																																																																																	
69	69.5	Clay, tan - hard																																																																																																	
69.5	75	Sand & gravel, very fine to fine w/thin clay streak @ 72'																																																																																																	
75	76	Clay, tan																																																																																																	
76	86	Sand & gravel, fine to very fine																																																																																																	
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 6/28/88 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 8/2/88 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>[Signature]</i>																																																																																																			
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.																																																																																																			