


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Section SE 1/4 NE 1/4	Section number 22	Township number T 28 S R 1W E/W	Range number
2. Distance and direction from nearest town or city: SE. corner of 47th South & Ridge Road Street address of well location if in city: Goddard, Kansas			3. Owner of well: L&M Enterprises R.R. or street: 329 East Second City, state, zip code: Goddard, Kansas			
Locate with "X" in section below: 			Sketch map:			
5. Type and color of material			From	To	6. Bore hole dia. 11 in. Completion date 6-29-77 Well depth 75 ft.	
Topsoil			0	2	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Clay			2	18	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Fine Sand with Clay Balls			18	50	9. Casing: Styrene Height: Above or below/ Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight 12 lbs./ft. Dia. 5 in. to 75 ft. depth Wall Thickness: inches or Dia. 5 in. to 75 ft. depth gage No. 200	
Medium Sand			50	75	10. Screen: Manufacturer's name Sunflower Plastic Type Styrene Dia. 5" Slot/gauge .06 Length 20' Set between 55 ft. and 75 ft. ft. and 75 ft. Gravel pack? yes Size range of material 1/2-1/8"	
					11. Static water level: 45 ft. below land surface Date 6-29-77 mo./day/yr.	
					12. Pumping level below land surfaces: ft. after 12 hrs. pumping 12 g.p.m. ft. after 12 hrs. pumping 12 g.p.m. Estimated maximum yield 12 g.p.m.	
					13. Water sample submitted: 12 mo./day/yr. ☐ Yes ☐ No Date 6-29-77	
					14. Well head completion: ☒ Pitless adapter 12 inches above grade	
					15. Well grouted? yes 1 to 2 fine sand mix. With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.	
					16. Nearest source of possible contamination: Septic ft. 100 Direction North Type Tank Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: ☐ Not installed Manufacturer's name Sta-Rite Model number 20P4C01 HP 1/2 Volts 110 Length of drop pipe 65 ft. capacity 20 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
			(Use a second sheet if needed)			
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas Signed M. Arnold Date 6-29-77 Authorized representative				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5