


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

☒ Location of well:	County Sedgewick	Fraction SE 1/4 SW 1/4 SW 1/4	Section number 27	Township number T 21 S	Range number R 1																																																
☒ Distance and direction from nearest town or city: 3 miles South of Wichita International Air port Street address of well location if in city:			3. Owner of well: Vulcan Materials Co. R.R. or street: 6200 So. Ridge Road--P.O. Box 545 City, state, zip code: Wichita, KS 67201																																																		
4. Locate with "X" in section below: N  S 1 Mile Sketch map: No. 30 -- 16" Monitor Well, 1150' East and 150' North of SW Corner Sec. 27 (Approx.)			6. Bore hole dia. 24 in. Completion date 10-14-77 Well depth 74 ft.																																																		
5. Type and color of material <table border="1" style="width:100%; border-collapse: collapse; margin-top: 5px;"> <thead> <tr> <th></th> <th>From</th> <th>To</th> </tr> </thead> <tbody> <tr><td>Top soil & fill</td><td>0</td><td>2</td></tr> <tr><td>Fill - trash - limestone, brown clay</td><td>2</td><td>7</td></tr> <tr><td>Clay, gray</td><td>7</td><td>10</td></tr> <tr><td>Clay, silty, brown</td><td>10</td><td>15</td></tr> <tr><td>Clay, sandy, red & brown</td><td>15</td><td>19</td></tr> <tr><td>Sand, & gravel, fine to coarse with thin clay streaks</td><td>19</td><td>35</td></tr> <tr><td>Clay, silty, brown & gray</td><td>35</td><td>55</td></tr> <tr><td>Sand & gravel, fine to coarse, cemented?</td><td>55</td><td>60</td></tr> <tr><td>Sand & gravel, fine to coarse</td><td>60</td><td>68</td></tr> <tr><td>Clay, brown & gray</td><td>68</td><td>73</td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>				From	To	Top soil & fill	0	2	Fill - trash - limestone, brown clay	2	7	Clay, gray	7	10	Clay, silty, brown	10	15	Clay, sandy, red & brown	15	19	Sand, & gravel, fine to coarse with thin clay streaks	19	35	Clay, silty, brown & gray	35	55	Sand & gravel, fine to coarse, cemented?	55	60	Sand & gravel, fine to coarse	60	68	Clay, brown & gray	68	73																7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
	From	To																																																			
Top soil & fill	0	2																																																			
Fill - trash - limestone, brown clay	2	7																																																			
Clay, gray	7	10																																																			
Clay, silty, brown	10	15																																																			
Clay, sandy, red & brown	15	19																																																			
Sand, & gravel, fine to coarse with thin clay streaks	19	35																																																			
Clay, silty, brown & gray	35	55																																																			
Sand & gravel, fine to coarse, cemented?	55	60																																																			
Sand & gravel, fine to coarse	60	68																																																			
Clay, brown & gray	68	73																																																			
(Use a second sheet if needed)			8. Use: ☐ Domestic ☐ Public supply ☒ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other																																																		
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley			9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface .90' RMP ☐ PVC ☐ Weight 42.05 lbs./ft. Dia. 16 in. to 57 ft. depth Wall Thickness: inches or Dia. 16 in. to 74 ft. depth gauge No. .250																																																		
19. Remarks: Elev. Top of Casing - 1313.9 Elev. Ground 1313.0 Well moved from test hole approximately 100' east. test hole grouted.			10. Screen: Manufacturer's name Doerr Armco Ingot Type Double-slot Dia. 16" Slot gauge 1/8" Length 12' Set between 57 ft. and 69 ft. Gravel pack? yes Size range of material 3/8-200																																																		
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS 67530 Signed <i>[Signature]</i> Date 2-14-78 Authorized representative																																																					

Forward the white, blue and pink copies to the Department of Health and Environment

Farm WWC-5