

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82g-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

X Location of well:	County Sedgwick	Fraction NE 1/4 SE 1/4 SW 1/4	Section number 27	Township number T 28 S	Range number R 1 E																																																
Distance and direction from nearest town or city: 3 miles South of Wichita International Airport Street address of well location if in city:			3. Owner of well: Vulcan Materials Company R.R. or street: 6200 So. Ridge Road - Box 545 City, state, zip code: Wichita, KS 67201																																																		
4. Locate with "X" in section below: Sketch map: NO. 33 -- 16" Monitor Well (South - Shallow) 2400' East & 900' North of SW Corner Sec. 27			6. Bore hole dia. <u>24</u> in. Completion date <u>10-6-77</u> Well depth <u>65</u> ft.																																																		
5. Type and color of material			7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary																																																		
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th style="width:80%;"></th> <th style="width:10%;">From</th> <th style="width:10%;">To</th> </tr> </thead> <tbody> <tr> <td>Fill, top soil, trash, red clay</td> <td>0</td> <td>8</td> </tr> <tr> <td>Clay, brown & gray</td> <td>8</td> <td>13</td> </tr> <tr> <td>Clay, silty, brown</td> <td>13</td> <td>20</td> </tr> <tr> <td>Sand & gravel, fine to coarse</td> <td>20</td> <td>34</td> </tr> <tr> <td>Clay & silt, brown & gray</td> <td>34</td> <td>50</td> </tr> <tr> <td>Sand & gravel, fine to coarse</td> <td>50</td> <td>60</td> </tr> <tr> <td>Clay, brown & gray (Some silt)</td> <td>60</td> <td>65</td> </tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>				From	To	Fill, top soil, trash, red clay	0	8	Clay, brown & gray	8	13	Clay, silty, brown	13	20	Sand & gravel, fine to coarse	20	34	Clay & silt, brown & gray	34	50	Sand & gravel, fine to coarse	50	60	Clay, brown & gray (Some silt)	60	65																									8. Use: ☐ Domestic ☐ Public supply ☒ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
	From	To																																																			
Fill, top soil, trash, red clay	0	8																																																			
Clay, brown & gray	8	13																																																			
Clay, silty, brown	13	20																																																			
Sand & gravel, fine to coarse	20	34																																																			
Clay & silt, brown & gray	34	50																																																			
Sand & gravel, fine to coarse	50	60																																																			
Clay, brown & gray (Some silt)	60	65																																																			
(Use a second sheet if needed)			9. Casing: Material <u>steel</u> Height: <u>Above</u> or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>42.05</u> lbs./ft. Dia. <u>16</u> in. to <u>53</u> ft. depth Wall Thickness: inches or Dia. <u>16</u> in. to <u>65</u> ft. depth gage No. <u>.250</u>																																																		
10. Screen: Manufacturer's name <u>Doerr</u> <u>Armco Ingot</u> Type <u>Double-slot</u> Dia. <u>16"</u> Slot gauge <u>1/8</u> Length <u>8'</u> Set between <u>53</u> ft. and <u>61</u> ft. Gravel pack? <u>yes</u> Size range of material <u>3/8-200</u>			11. Static water level: <u>52.5</u> ft. below land surface Date <u>11-7-77</u>																																																		
12. Pumping level below land surfaces: <u>62</u> ft. after <u>4</u> hrs. pumping <u>38</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>38</u> g.p.m.			13. Water sample submitted: <u> </u> mo./day/yr. ☐ Yes ☒ No Date <u> </u>																																																		
14. Well head completion: ☐ Pitless adapter <u>NO</u> inches above grade			15. Well grouted? <u>yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>50</u> ft.																																																		
16. Nearest source of possible contamination: <u> </u> ft. <u>Plant</u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? ☐ Yes ☒ No			17. Pump: ☒ Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																																																		
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley	19. Remarks: Elev. Top 16" Casing <u>1311.78</u> Elev. Ground <u>1311.27</u>		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name <u>Great Bend, KS 67530</u> License No. <u> </u> Address <u> </u> Signed <u>D.W. Clarke</u> Date <u>2-14-</u> Authorized representative																																																		

Forward the white, blue and pink copies to the Department of Health and Environment

Farm WWC-5