


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

X Location of well:		County Sedgwick	Fraction NE 1/4 SE 1/4 SW 1/4	Section number 27	Township number T 28 S	Range number R 1
X Distance and direction from nearest town or city: 3 miles South of Wichita International Airport Street address of well location if in city:				3. Owner of well: Vulcan Materials Co. R.R. or street: 6200 So. Ridge Road - P.O. Box 545 City, state, zip code: Wichita, KS 67201		
4. Locate with "X" in section below: Sketch map: No. 34 - 16" monitor well - (North-Deep) 2400' East - 920' North of SW Corner Section 27				6. Bore hole dia. 24 in. Completion date 10-7-77 Well depth 80 ft.		
				7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
				8. Use: Domestic ☐ Public supply ☒ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other ☐		
5. Type and color of material				From	To	9. Casing: Material Steel Height Above or below Threaded ☐ Welded ☒ Surface .51 in. RMP ☐ PVC ☐ Weight 42.05 lbs./ft. Dia. 16 in. to 67 ft. depth Wall Thickness: inches or Dia. 16 in. to 80 ft. depth gauge No. .250
Fill, top soil, trash, red clay				0	8	10. Screen: Manufacturer's name Doerr Armco Ingot Type Double-slot Dia. 16" Slot/gauze 1/8" Length 8' Set between 70 ft. and 78 ft. ft. and 78 ft. Gravel pack? yes Size range of material 3/8-200
Clay, brown & gray				8	13	11. Static water level: 50.5 ft. below land surface Date 11-16-77
Clay, silty, brown				13	20	12. Pumping level below land surfaces: 75 ft. after 4 hrs. pumping 32 g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 32 g.p.m.
Sand & gravel, fine fine to coarse				20	34	13. Water sample submitted: mo./day/yr. Yes ☒ No ☐ Date
Clay & silt, brown & gray				34	50	14. Well head completion: Pitless adapter NO Inches above grade
Sand & gravel, fine to coarse				50	60	15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 67 ft.
Clay, brown & gray (some silt)				60	69	16. Nearest source of possible contamination: PLANT ft. Direction Type Well disinfected upon completion? Yes ☒ No ☐
Fine sand				69	74	17. Pump: ☒ Not installed Manufacturer's name Model number HP Volts Length of drop pipe ft. capacity g.p.m. Type: Submersible Turbine Jet Reciprocating Centrifugal Other
Clay, silty, brown brown				74	80	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq. Inc. 185 Business name Great Bend, KS 67530 License No. Address Signed Date 2-14-78 Authorized representative
18. Elevation: Topography: Hill Slope Upland Valley				19. Remarks: Elev. Top 16" Casing - 1312.14 Elev.  Ground - 1311.27		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5