

1 LOCATION OF WATER WELL: County: Sedgwick		Fraction NE 1/4 SW 1/4 NE 1/4		Section Number 33	Township Number T 28 S	Range Number R 1 E
Distance and direction from nearest town or city street address of well if located within city? 2500' S. of 6200 South Ridge Road; Wichita, KS MW-9C (40885067)						
2 WATER WELL OWNER: Vulcan Chemicals RR#, St. Address, Box #: P.O. Box 12283 City, State, ZIP Code: Wichita, KS 67277 Board of Agriculture, Division of Water Resources Application Number:						
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL 41.5 ft. ELEVATION: Approximate Surface: 1305 Depth(s) Groundwater Encountered 1. 38 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 38.6 ft. below land surface measured on mo/day/yr 4/28/88 Pump test data: Well water was ft. after hours pumping gpm Est. Yield N/A gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 10 in. to 42 ft. and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 5 Public water supply 8 Air conditioning 11 Injection well 2 Irrigation 4 Industrial 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 7 Lawn and garden only 10 Observation well Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No X				
5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded 7 Fiberglass Stainless Steel Threaded X Blank casing diameter 2 in. to 36.5 ft. Dia in. to ft. Dia in. to ft. Casing height above land surface 42 in., weight lbs./ft. Wall thickness or gauge No. Schedule 5/40 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 2 Stainless steel 3 Fiberglass 4 PVC 5 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify) 9 ABS 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 2 Mill slot 3 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) SCREEN-PERFORATED INTERVALS: From 36.5 ft. to 41.5 ft. From ft. to ft. GRAVEL PACK INTERVALS: From 34 ft. to 42 ft. From ft. to ft. FROM TO LITHOLOGIC LOG FROM TO LITHOLOGIC LOG 0 5 Dark Gray Lean Clay, Trace Sand 5 10 Olive-Gray Sandy Clay 10 17 Light Red-Brown Silty Sandy Clay 17 20 Red-Brown Clayey Sand 20 25 Light Red-Brown Silty Medium to Coarse Sand 25 30 Light Tan Silty Fine to Medium Sand 30 35 Light Tan and Red Sandy Silt 35 38 Grayish Tan Silty Clay 38 40 Gray-Tan Silty Sandy Clay 40 42 Light Gray Sandy Silt						
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Grout Intervals: From 0 ft. to 31 ft. From 31 ft. to 34 ft. From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) Landfill Direction from well? Northeast How many feet? 2000						
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 4/19/88 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 416 This Water Well Record was completed on (mo/day/yr) 6-13-88 under the business name of Ternacon Consultants, Inc. by (signature)						
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.						