

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Sedg.</u>	Fraction <u>center of</u> 1/4 1/4 NW 1/4	Section number <u>36</u>	Township number <u>T 28 S</u>	Range number <u>R 1 E</u>
2. Distance and direction from nearest town or city: Street address of well location if in city: <u>1 W. Haysville</u>			3. Owner of well: <u>John Hay</u> R.R. or street: <u>3705 W 63 South</u> City, state, zip code: <u>Wichita, KS</u>			
4. Locate with "X" in section below: N W E S 1 Mile Sketch map: <u>open field</u>			6. Bore hole dia. <u>30</u> in. Completion date <u>6/30/79</u> Well depth <u>54</u> ft.			
			7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary			
			8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other			
5. Type and color of material			From	To	9. Casing: Material <u>C-Asb</u> Height: Above or below Threaded ☐ Welded ☐ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>13</u> lbs./ft. Dia. <u>16</u> in. to <u>54</u> ft. depth Wall Thickness: inches or Dia. <u>16</u> in. to <u>54</u> ft. depth gage No. <u>3/4</u>	
<u>Topsoil</u>			<u>0</u>	<u>1</u>	10. Screen: Manufacturer's name <u>Johnson</u> Type <u>Cem. Asb.</u> Dia. <u>16</u> in. Slot/gauze <u>4/4</u> Length <u>13</u> ft. Set between <u>4</u> ft. and <u>54</u> ft. Gravel pack? ☒ Size range of material <u>3/8</u>	
<u>Fine Sand</u>			<u>1</u>	<u>4</u>	11. Static water level: <u>16</u> ft. below land surface Date <u>6/15/79</u> mo./day/yr.	
<u>Clay</u>			<u>4</u>	<u>10</u>	12. Pumping level below land surfaces: <u>23</u> ft. after <u>1</u> hrs. pumping <u>500</u> g.p.m. ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>800</u> g.p.m.	
<u>Med. Sand</u>			<u>10</u>	<u>25</u>	13. Water sample submitted: <u> </u> mo./day/yr. Yes ☐ No ☒ Date <u> </u>	
<u>Good Gravel</u>			<u>25</u>	<u>54</u>	14. Well head completion: ☐ Pitless adapter <u>12</u> inches above grade	
					15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.	
					16. Nearest source of possible contamination: <u>none</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <u> </u> Yes ☒ No	
					17. Pump: <u> </u> Not installed Manufacturer's name <u>Peerless</u> Model number <u>8941</u> HP <u>40</u> Volts <u> </u> Length of drop pipe <u>40</u> ft. capacity <u>750</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
18. Elevation:			19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Weninger Irrigation</u> <u>238</u> Business name License No. Address <u>Maize</u> Signed <u>K. Weninger</u> Date <u>4/2/80</u> Authorized representative	
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5