

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick NE	Fraction SE 1/4 SW 1/4	Section number 27	Township number T 28 S	Range number R 1 E
2. Distance and direction from nearest town or city: Street address of well location if in city:				3. Owner of well: Vulcan Materials Company R.R. or street: Wichita, Kansas City, state, zip code:		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>12</u> in. Completion date <u>3/3/77</u> Well depth <u>63.6</u> ft.		
		Well No. 101B-1976 (North Well) + - 1000' N. of 63rd; + - 7' W. of East Fence		7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☒ Other		
Top soil		0	2	9. Casing: Material <u>PVC</u> Height: Above <u>2.60</u> in. Threaded ☐ Welded ☐ Surface <u>2.60</u> in. RMP ☐ PVC ☒ Weight <u>3.94</u> lbs./ft. Dia. <u>6</u> in. to <u>60.5</u> ft. depth Wall thickness: inches or Dia. <u>6</u> in. to <u>60.5</u> ft. depth gage No. <u>0.316</u> "		
Brown-gray clay		2	15	10. Screen: Manufacturer's name <u>Layne</u> Type <u>PVC</u> Dia. <u>6</u> " Slot/gauze <u>0.125</u> " Length <u>10</u> ' Set between <u>53.6</u> ft. and <u>63.6</u> ft. Gravel pack? <u>yes</u> Size range of material <u>1/4</u> "		
Fine to co. sand w/some co. gravel		15	28	11. Static water level: * <u>47.7</u> ft. below land surface Date <u>2/25/77</u> mo./day/yr.		
Brown clay		28	44	12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.		
Fine to co. sand		44	53	13. Water sample submitted: _____ mo./day/yr. Yes ☒ No ☐ Date _____		
Brown clay		53	61	14. Well head completion: _____ Pitless adapter _____ Inches above grade		
Fine to co. sand to fine gravel		61	68	15. Well grouted? <u>yes</u> With: ☒ Neat cement _____ Bentonite _____ Concrete _____ Depth: From <u>0</u> ft. to <u>43.6</u> ft.		
Brown silt		68	73	16. Nearest source of possible contamination: **ND ft. _____ Direction _____ Type _____ Well disinfected upon completion? Yes ☒ No ☐		
Brown clay		73	85	17. Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
Med. to co. sand to med.co. gravel		85	95	18. Elevation: 1307.33		
Blue--gray limey shale		95	100	19. Remarks: Static water level is from top of casing; also screen setting depth & well depth.		
(Use a second sheet if needed)				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name _____ License No. _____ Address <u>Wichita, Kansas</u> Signed <u>[Signature]</u> Date <u>3/8/77</u>		
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley		**Not Determined				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5