

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction NW 1/4 NW 1/4 1/4	Section number 27	Township number T 28 S	Range number R 1 E/W
2. Distance and direction from nearest town or city: Street address of well location if in city:				3. Owner of well: R.R. or street: City, state, zip code:		
4. Locate with "X" in section below: N W E S 1 Mile				Sketch map: Monitor & Sampling Well No. 106A - 1976 (South Well) 52' South of 55th St. & 59' East of Ridge Rd.		
5. Type and color of material				From	To	6. Bore hole dia. <u>12</u> in. Completion date _____ Well depth <u>86.4</u> ft. <u>3/3/77</u>
Top soil				0	2	7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
Brown clay				2	13	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☒ Other
Silty med. to co. gravel & sand				13	44	9. Casing: Material <u>PVC</u> Height: Above _____ Threaded _____ Welded _____ Surface <u>3.5</u> in. RMP _____ PVC ☒ Weight <u>3.94</u> lbs./ft. Dia. <u>6</u> in. to <u>77</u> ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. <u>0.316</u> "
Fine to co. sand to med. gravel				44	54	10. Screen: Manufacturer's name _____ <u>Layne</u> Type <u>PVC</u> Dia. <u>6</u> " Slot/gauze <u>0.125</u> " Length <u>10</u> ' Set between <u>76</u> ft. and <u>86.0</u> ft. Gravel pack? ☒ Size range of material <u>1/4</u> " ft.
Brown clay				54	71	11. Static water level: * _____ mo./day/yr. <u>47.7</u> ft. below land surface Date <u>2/25/77</u>
Silty fine to coarse sand to fine gr.				71	86	12. Pumping level below land surfaces: _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.
Med. fine to co. sand to med. fine gr.				86	97	13. Water sample submitted: _____ mo./day/yr. Yes ☒ No ☐ Date _____
Blue-gray shale				97	100	14. Well head completion: ☐ Pitless adapter _____ Inches above grade
						15. Well grouted? <u>yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>66</u> ft.
						16. Nearest source of possible contamination: <u>**ND</u> ft. _____ Direction _____ Type _____ Well disinfected upon completion? Yes ☒ No ☐
						17. Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)						
18. Elevation: 1310.74 Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley		19. Remarks: *Static Water Level is from top of casing; also screen setting depth & well depth. **ND - not determined		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name <u>Wichita, Kansas</u> License No. _____ Address _____ Signed <u>[Signature]</u> 3/8/77 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5