

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction SE 1/4 NE 1/4 1/4	Section number 33	Township number T 28 S	Range number R 1 E/W				
2. Distance and direction from nearest town or city: Street address of well location if in city:				3. Owner of well: R.R. or street: City, state, zip code:						
4. Locate with "X" in section below: N W E S 1 Mile				Sketch map: <table border="1" style="width: 100px; height: 100px; text-align: center; border-collapse: collapse;"> <tr><td>NW</td><td>NE</td></tr> <tr><td>SW</td><td>SE</td></tr> </table> Monitor & Sampling Well No. 109B- 1976 (Southwest) 0.3 Mi. South of 63rd St. & 156' West of Ridge Rd.			NW	NE	SW	SE
NW	NE									
SW	SE									
5. Type and color of material				From	To					
Top soil				0	2					
Sandy clay				2	7					
Red clay				7	10					
Fine to co. sand				10	31					
Buff clay				31	32					
Med. to co. sand				32	36					
Buff clay				36	44					
Coarse sand to fine gravel				44	53					
Fine to med. sand w/clay lenses				53	58					
Fine sand w/very thin clay lenses				58	69					
Coarse sand to fine gravel				69	85					
Brown clay				85	101					
Very coarse sand - fine gravel				101	111					
Blue shale				111						
(Use a second sheet if needed)										
18. Elevation: 1307.31' Topography: Hill Slope Upland ☒ Valley		19. Remarks: * Static Water Level is from top of casing; also screen setting depth & well depth. ** ND = not determined								
6. Bore hole dia. <u>12</u> in. Completion date <u>3/3/77</u> Well depth <u>58.7</u> ft.										
7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary										
8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☒ Other										
9. Casing: Material <u>PVC</u> Height: Above or below <u>503</u> Threaded ☐ Welded ☐ Surface <u>2.0'</u> in. RMP ☐ PVC ☒ Weight <u>3.94</u> lbs./ft. <u>6</u> in. to <u>49</u> ft. depth Wall Thickness: inches of <u>0.316</u> Dia. <u>6</u> in. to <u>49</u> ft. depth gage No. <u>0.316</u>										
10. Screen: Manufacturer's name <u>Layne</u> Type <u>PVC</u> Dia. <u>6"</u> Slot/gauze <u>0.125"</u> Length <u>10'</u> Set between <u>48.7'</u> ft. and <u>58.7'</u> ft. ft. and <u>1/4"</u> ft. Gravel pack? <u>yes</u> Size range of material <u>1/4"</u>										
11. Static water level: * <u>51</u> ft. below land surface Date <u>12/9/76</u> <u>51</u> ft. below land surface Date <u>12/9/76</u>										
12. Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.										
13. Water sample submitted: <u>Yes</u> ☒ No ☐ Date <u>mo./day/yr.</u>										
14. Well head completion: ☐ Pitless adapter <u> </u> inches above grade										
15. Well grouted? <u>yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>40</u> ft.										
16. Nearest source of possible contamination: **ND ft. Direction Type Well disinfected upon completion? <u>Yes</u> ☒ No ☐										
17. Pump: ☒ Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other										
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Layne Western Co. 102</u> Business name <u>Wichita, Kansas</u> License No. <u> </u> Address <u> </u> Signed <u> </u> 3/8/77 Authorized representative										

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5