


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction NE 1/4 NW 1/4	Section number 34	Township number T 29 S	Range number R 26 E
2. Distance and direction from nearest town or city: Street address of well location if in city:				3. Owner of well: Vulcan Materials Co. R.R. or street: Wichita, Kansas City, state, zip code:		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>12</u> in. Completion date <u>3/3/77</u> Well depth <u>85.9</u> ft.		
		Monitor & Sampling Well No. 102A - 1976 (West Well) 1/2 Mi. East of Ridge R. & 26' South of 63rd St.		7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material				From	To	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☒ Other
Top soil				0	2	9. Casing: Material <u>PVC</u> Height: Above <u>surface</u> Threaded ☐ Welded ☐ Surface <u>2.1</u> in. RMP ☐ PVC ☒ Weight <u>3.94</u> lbs./ft. Dia. <u>6</u> in. to <u>7.5</u> ft. depth Wall thickness: <u>0.316</u> in. or Dia. <u>6</u> in. to <u>7.5</u> ft. depth gage No. <u>0.316</u>
Brown clay & gray clay & tight				2	15	10. Screen: Manufacturer's name <u>Layne</u> Type <u>PVC</u> Dia. <u>6"</u> Slot/gauze <u>0.125"</u> Length <u>10'</u> Set between <u>75.9</u> ft. and <u>85.9</u> ft. Gravel pack? <u>yes</u> Size range of material <u>1/4"</u>
Fine to co. sand & gravel				15	28	11. Static water level: * <u>50.0</u> ft. below land surface Date <u>2/25/77</u>
Brown clay				28	41	12. Pumping level below land surfaces: ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield ____ g.p.m.
Fine to co. sand				41	53	13. Water sample submitted: ____ mo./day/yr. ____ Yes ☒ No Date ____
Brown clayey silt				53	74	14. Well head completion: ____ Pitless adapter ____ Inches above grade
Fine to co. sand to fine gravel				74	79	15. Well grouted? <u>yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>65.9</u> ft.
Brown clay				79	81	16. Nearest source of possible contamination: <u>**ND</u> ____ Direction ____ Type ____ Well disinfected upon completion? ____ Yes ☒ No
Med. to co. sand to med. co. gravel				81	93	17. Pump: ☒ Not installed Manufacturer's name ____ Model number ____ HP ____ Volts ____ Length of drop pipe ____ ft. capacity ____ g.p.m. Type: ____ Submersible ____ Turbine ____ Jet ____ Reciprocating ____ Centrifugal ____ Other
Blue-gray shale - limey				93	98	18. Elevation: 1304.59 Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley
(Use a second sheet if needed)				19. Remarks: * Static Water Level is from top of casing; also screen setting depth & well depth. ** Not Determined		
				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name License No. Address Wichita, Kansas Signed <u>[Signature]</u> Date <u>3/8/77</u>		

Forward the white, blue and pink copies to the Department of Health and Environment