

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Pratt	Fraction 1/4 1/4 NW 1/4	Section number 8	Township number T 28 S	Range number R 11 W 4W
2. Distance and direction from nearest town or city: 1 Mile South of Cairo Street address of well location if in city:			3. Owner of well: Lester Goyen R.R. or street: Cairo, Kansas City, state, zip code:			
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile			Sketch map: Well No. 1		6. Bore hole dia. 30 in. Completion date 5-27-77 Well depth 143 ft.	
5. Type and color of material			From To		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
					8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
Top soil			0 3		9. Casing: Material Stl. Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 31.75 lbs./ft. Dia. 16 in. to 80 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 188 "	
					10. Screen: Manufacturer's name Doerr Metal Products Type Steel Dia. 16" Slot/gauze 1/8 Length 64' Set between 79 ft. and 143 ft. ft. and <input type="checkbox"/> ft. Gravel pack? yes Size range of material 1/8x1/2	
Med to co. sand & gravel-full clay			3 28		11. Static water level: <input type="checkbox"/> mo./day/yr. 21 ft. below land surface Date 5-27-77	
Clay			28 45		12. Pumping level below land surfaces: 67 ft. after 4 hrs. pumping 1002 g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 1400 g.p.m.	
Med. to co. sand & gravel			45 62		13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>	
Clay			62 72		14. Well head completion: <input type="checkbox"/> Pitless adapter 12 inches above grade	
Fine to co. sand w/clay			72 76		15. Well grouted? yes With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.	
Fine to co. sand & gravel			76 86		16. Nearest source of possible contamination: ft. 1400 Direction NW Type Farm Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Clay			86 95		17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Layne & Bowler Model number 12KLM HP 80 Volts <input type="checkbox"/> Length of drop pipe 100 ft. capacity 800 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
Sandy clay			95 99		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name Wichita, Kansas License No. <input type="checkbox"/> Address Wichita, Kansas Signed [Signature] Date 6-1-77 Authorized representative	
Med. to co. sand & gravel			99 110			
Fine to co. sand w/clay			110 114			
Gray clay			114 119			
Sandy clay			119 121		21. (Use a second sheet if needed)	
Fine to co. sand & gravel			121 143			
Red shale			✓ 143 146			
18. Elevation: 1770 Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley		19. Remarks: 29688 28 11 8 NBX				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5