


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Pratt	Fraction 1/4 1/4 CNE 1/4	Section number 20	Township number T 28 S	Range number R 11 W
2. Distance and direction from nearest town or city: 12 1/2 miles Southeast of Pratt, KS Street address of well location if in city:			3. Owner of well: Willard B. Thompson R.R. or street: Box 997 City, state, zip code: Wichita, KS 67201		
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile			Sketch map: 		
5. Type and color of material			From	To	6. Bore hole dia. 24 in. Completion date 5-13-77 Well depth 196 ft.
Top soil & brown clay			0	7	7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
Sand & gravel			7	17	8. Use: Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> <input checked="" type="checkbox"/> Irrigation Air conditioning <input type="checkbox"/> Stock Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Brown & white clay & limestone			17	33	9. Casing: Material Steel Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 30.3 lbs./ft. SEE REMARKS ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 7 ga.
Sand & gravel			33	71	10. Screen: Manufacturer's name Doerr Type Double-slot Dia. 16" Slot gauge 1/8" Length 80' Set between SEE REMARKS ft. Gravel pack? yes Size range of material 3/8-200
Brown clay			71	74	11. Static water level: <input type="checkbox"/> mo./day/yr. 60 ft. below land surface Date 4-12-77
Sand & gravel & clay streaks at 104'			74	115	12. Pumping level below land surfaces: N/C ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <input type="checkbox"/> g.p.m.
Sandy clay			115	120	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. Yes <input checked="" type="checkbox"/> No Date
Sand & gravel			120	128	14. Well head completion: <input type="checkbox"/> Pitless adapter 12 inches above grade
Brown & white clay & limestone			128	136	15. Well grouted? yes With XX Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete <input type="checkbox"/> Depth: From 0 ft. to 10 ft.
Sand & gravel & thin clay streaks			136	157	16. Nearest source of possible contamination: FIELD ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Brown & blue clay & sand streaks between 164' & 172'			157	183	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name Peerless Pump Model number 12LB-4 HP 100 Volts <input type="checkbox"/> Length of drop pipe 110 ft. capacity 900 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
Sand & gravel			183	195	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name <input type="checkbox"/> License No. <input type="checkbox"/> Address Great Bend, KS 67530 Signed [Signature] Date 5-16-77 Authorized representative
Limestone & red shale			195	196	
(Use a second sheet if needed)					
18. Elevation: 1825 Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley	19. Remarks: CASING & SCREEN RECORD: Plain casing 29404 Doerr Screen Plain casing 28 11 20 NAX Doerr Screen Plain casing Doerr Screen		0	90	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5