


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County PRATT	Fraction NW 1/4 SE 1/4 NW 1/4	Section number 4	Township number T 28 S	Range number R 12 W E/W
2. Distance and direction from nearest town or city: 5 1/2 E of Pratt, KS			3. Owner of well: PAUL MONA			
Street address of well location if in city:			City, state, zip code: PRATT, KS			
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 		6. Bore hole dia. 10 in. Completion date 10 Oct 78 Well depth 135 ft.	
5. Type and color of material			From		To	
			Soil		0 2	
			Clay, Tan & Caliche		2 20	
			Clay, Tan & White		20 32	
			Sand, fine to med		32 41	
Sand, fine to med & fine gravel			41 115		7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
Sand, med to Coarse & gravel			115 135		8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
					9. Casing: Material <input type="checkbox"/> Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia 5 in. to 115 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 258	
					10. Screen: Manufacturer's name peerless Type saw slot Dia. 5 " Slot/gauze 1/8 Length 20' Set between 115 ft. and 135 ft. ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 1/4 X 1/4	
					11. Static water level: <input type="checkbox"/> mo./day/yr. 79 ft. below land surface Date 10 Oct 78	
					12. Pumping level below land surfaces: ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 50 g.p.m.	
					13. Water sample submitted: <input type="checkbox"/> mo./day/yr. Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>	
					14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter 12 Inches above grade	
					15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 4 ft. to 14 ft.	
					16. Nearest source of possible contamination: NONE ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
					17. Pump: <input type="checkbox"/> Not installed Manufacturer's name STARITE Model number 20 HP 3/4 Volts <input type="checkbox"/> Length of drop pipe 100 ft. capacity 20 g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
18. Elevation:			19. Remarks:		20. Water well contractor's certification:	
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley			4' x 4' x 4" slab poured below pitless adapter		This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Central well & pump 325 Business name 121 S. Taylor Pratt KS License No. <input type="checkbox"/> Address 121 S. Taylor Pratt KS Signed Monomick Date 1 Nov 78 Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5