

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 076 PRATT NW 1/4 NE 1/4 NE 1/4 18 T 28 S R 14 W

Distance and direction from nearest town or city street address of well if located within city?
1 MILES SOUTH AND 3/4 MILE EAST OF CULLISON

2 WATER WELL OWNER: JOHN DAUNER 367
RR#, St. Address, Box #: R.R. 1, BOX 41-LL Board of Agriculture, Division of Water Resources
City, State, ZIP code : PRATT, KS 67124- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

/ \			X
1	NW	NE	
M			
i	W	E	
l			
e	SW	SE	
\ /			

4 DEPTH OF COMPLETED WELL 160 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 109 ft. 2. 0 ft. 3. 0 ft.
WELL'S STATIC WATER LEVEL 109 ft. below land surface measured on mo/day/yr 08/30/96
Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 8 .75 in. to 160 ft., and in. to 0 ft.
WELL WATER TO BE USED AS: 01 DOMESTIC
Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 140 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 24 in., weight 0 lbs/ft. Wall thickness or gauge No. 26
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 160 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS: From 135 ft. to 160 ft., From 0 ft. to 0 ft.
From 25 ft. to 130 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 5 ft. to 25 ft., From 130 ft. to 135 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: 01 SEPTIC TANK
Direction from well? WEST SOUTH WEST How many feet? 200

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	64	TAN CLAY			
64	126	05 SAND 17 GRAVEL			
126	138	TAN CLAY			
138	160	05 SAND 17 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/30/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 08/30/96 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse