

USE TYPEWRITER OR BALL  
POINT PEN—PRESS FIRMLY,  
PRINT CLEARLY.

**WATER WELL RECORD**  
**KSA 82a-1201-1215**

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

County <b>Pratt</b>		Fraction <b>1/4 1/4 CSW 1/4</b>		Section number <b>12</b>		Township number <b>T 28 S</b>		Range number <b>R 14 EW</b>	
2. Distance and direction from nearest town or city: <b>5 1/2 miles SW of Pratt, KS.</b> Street address of well location if in city:					3. Owner of well: <b>Elwood Lawrence</b> R.R. or street: <b>Route 4</b> City, state, zip code: <b>Pratt, KS 67124</b>				
4. Locate with "X" in section below: <div style="text-align: center;"> </div>					Sketch map:				
5. Type and color of material					From		To		6. Bore hole dia. <b>24</b> in. Completion date <b>6-11-76</b> Well depth <b>123</b> ft.
top soil					0		2		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
brown & white clay & limestone					2		7		8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
sand & gravel & cemented streaks					7		17		9. Casing: Material <b>Steel</b> Height <b>Above</b> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>30.3</b> lbs./ft. Dia. <b>16</b> in. to <b>83</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth Gauge No. <b>7 ga.</b>
brown & white clay, sand & limestone					17		46		10. Screen: Manufacturer's name <b>Doerr</b> Type <b>Double-slot</b> Dia. <b>16"</b> <input checked="" type="checkbox"/> Slot gauge <b>1/8"</b> Length <b>40'</b> Set between <b>83</b> ft. and <b>123</b> ft. Gravel pack? <b>yes</b> Size range of material <b>3/8-200</b>
sand & gravel & cemented streaks					46		75		11. Static water level: <b>46'</b> mo./day/yr. ft. below land surface Date <b>6-3-76</b>
Red & gray clay					75		83		12. Pumping level below land surfaces: <b>N/C</b> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <input type="checkbox"/> g.p.m.
sand & gravel					83		122		13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>
brown & gray clay					122		123		14. Well head completion: <input type="checkbox"/> Pitless adapter <b>12</b> inches above grade
									15. Well grouted? <b>yes</b> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.
									16. Nearest source of possible contamination: ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
									17. Pump: Manufacturer's name <b>FMC - Peerless</b> Model number <b>12LB-3</b> HP <b>80</b> Volts <b>---</b> Length of drop pipe <b>100</b> ft. capacity <b>900</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
(Use a second sheet if needed)									20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Clarke Well &amp; Equip. Inc. 185</b> Business name License No. <b>67530</b> Address <b>Great Bend, KS</b> Signed <b>D. W. Clarke</b> Date <input type="checkbox"/> Authorized representative
18. Elevation:		19. Remarks:							
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley									

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5