

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Pratt		NW 1/4 NW 1/4 NW 1/4	5	T 28 S	R 15 EW
Distance and direction from nearest town or city street address of well if located within city? 6E 2N OF HAVILAND, KS					
2 WATER WELL OWNER: Leonard Harper					
RR#, St. Address, Box #: Box 1246					
City, State, ZIP Code: Great Bend, Kansas 67530					
Board of Agriculture, Division of Water Resources Application Number:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 120 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 61 ft. 2. 61 ft. 3. 18 Nov. 82 ft.			
		WELL'S STATIC WATER LEVEL 61 ft. below land surface measured on mo/day/yr			
		Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Est. Yield 100 gpm; Well water was _____ ft. after _____ hours pumping _____ gpm			
		Bore Hole Diameter 10 in. to 120 ft., and _____ in. to _____ ft.			
		WELL WATER TO BE USED AS:			
		☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 11 Injection well ☐ Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well 12 Other (Specify below)			
		Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒ If yes, mo/day/yr sample was submitted _____			
		Water Well Disinfected? Yes ☒ No _____			
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued ☒ Clamped _____ ☒ PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded _____ 7 Fiberglass Threaded _____					
Blank casing diameter 5 in. to 100 ft., Dia. _____ in. to _____ ft., Dia. _____ in. to _____ ft.					
Casing height above land surface 12 in., weight _____ lbs./ft. Wall thickness or gauge No. 214					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel 3 Stainless steel 5 Fiberglass ☒ PVC 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify) _____ 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Gauzed wrapped ☒ Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) _____					
SCREEN-PERFORATED INTERVALS: From 100 ft. to 120 ft., From _____ ft. to _____ ft.					
GRAVEL PACK INTERVALS: From 14 ft. to 120 ft., From _____ ft. to _____ ft.					
6 GROUT MATERIAL: 1 Neat cement ☒ Cement grout 3 Bentonite 4 Other _____					
Grout Intervals: From 4 ft. to 14 ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:					
☒ Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) _____ 13 Insecticide storage					
Direction from well? South How many feet? 80'					
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	2	Soil, top			
2	18	Sand, fine to med			
18	45	Clay, brown and tan			
45	95	Sand, fine to coarse and fine gravel			
95	120	Sand, med to coarse and med to coarse gravel, loose			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 4 Dec 82 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 325 This Water Well Record was completed on (mo/day/yr) 27 Jan 83 under the business name of Central Well & Pump Inc. by (signature) <i>[Signature]</i>					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					

OFFICE USE ONLY

T

28

R

15

EW

SEC.

5

NW

1/4

NW

1/4

NW

1/4

NW

1/4