

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <u>Pratt</u>	Fraction <u>1/4 C 1/4 se 1/4</u>	Section number <u>31</u>	Township number <u>T 28 S</u>	Range number <u>R 15 E/W</u>				
2. Distance and direction from nearest town or city: <u>5 mi W 3 1/2 mi S. 4 mi N. of Cullison</u> Street address of well location if in city: <u>Ks.</u>			3. Owner of well: <u>A. A. Smith</u> R.R. or street: <u>Haviland, Ks. 67059</u> City, state, zip code:						
4. Locate with "X" in section below: Sketch map: <div style="text-align: center;">N 1 Mile W <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td>NW</td><td>NE</td></tr><tr><td>SW</td><td>SE</td></tr></table> E S 1 Mile</div>			NW	NE	SW	SE	6. Bore hole dia. <u>29</u> in. Completion date <u>4-26-77</u> Well depth <u>213</u> ft.		
NW	NE								
SW	SE								
			7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary						
			8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other						
			9. Casing: Material <u>          </u> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <u>          </u> PVC <input checked="" type="checkbox"/> Weight <u>          </u> lbs./ft. Dia. <u>16</u> in. to <u>213</u> ft. depth Wall Thickness: inches or Dia. <u>          </u> in. to <u>          </u> ft. depth gage No. <u>32.5 SDR</u>						
5. Type and color of material			From	To	10. Screen: Manufacturer's name <u>Peerless</u>				
Top soil			0	4	Type <u>plastic</u> Dia. <u>16</u>				
Brown clay			4	12	Slot/gauze <u>3/16</u> Length <u>60</u>				
White and brown clay			12	28	Set between <u>153</u> ft. and <u>213</u> ft.				
Sand and gravel medium coarse			28	48	Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>3/4-3/8-1/2</u>				
Sand and gravel coarse			48	98	11. Static water level: <u>83</u> ft. below land surface Date <u>1-20-77</u>				
Coarse sand and gravel w/ yellow brown clay and streaks of rock.			98	114	12. Pumping level below land surfaces: <u>90</u> ft. after <u>1</u> hrs. pumping <u>600</u> g.p.m. <u>100</u> ft. after <u>2</u> hrs. pumping <u>1000</u> g.p.m. Estimated maximum yield <u>1400</u> g.p.m.				
Sand and gravel some yellow clay			114	128	13. Water sample submitted: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <u>2-22-77</u>				
Sand and gravel			128	183	14. Well head completion: <input type="checkbox"/> Pitless adapter <u>          </u> inches above grade				
white clay			183	193	15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>20</u> ft.				
Sand			193	215	16. Nearest source of possible contamination: ft. <u>34</u> Direction <u>W</u> Type <u>septic tank</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No				
Yellow green clay and sand rock			215		17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>W.L.R.</u> Model number <u>5-120H</u> HP <u>50</u> Volts <u>          </u> Length of drop pipe <u>150</u> ft. capacity <u>900</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other				
(Use a second sheet if needed)									
18. Elevation: <u>2068</u>	19. Remarks: <u>28209</u> <u>28 15 31 NDX</u>								
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosencrantz-Bemis 134</u> Business name License No. Address <u>Great Bend, Ks.</u> Signed <u>[Signature]</u> Date <u>5/17/77</u> Authorized representative								

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5