

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: *Kiowa* SE 1/4 SE 1/4 NE 1/4 31 T 28 S R 16 W

Distance and direction from nearest town or city street address of well if located within city?
 3 1/2 S. OF HAVILAND, KS

2 WATER WELL OWNER: HARTS, LARRY 110 Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: R.R. Application Number:
 City, State, ZIP code: HAVILAND, KS 67059-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 148 ELEVATION:
 Depth(s) Groundwater Encountered 1. 95 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 95 ft. below land surface measured on mo/day/yr
 Pump test data: Well water was ft. after hours pumping gpm
 Estimated Yield gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 8.75 in. to 148 ft., and in. to ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: BLUED
 Blank casing diameter 5 in. to 138 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 138 ft. to 148 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 148 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 4 ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: 01 SEPTIC TANK
 Direction from well? SE How many feet? 100

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	6	SILT & SAND			
6	17	BROWN CLAY			
17	45	TAN CLAY			
45	148	05 SAND AND 17 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/13/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 12/15/91 under the business name of CARL HAYSE WATER WELL SVC by (signature) *Carl Hayse*