

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment
Division of Environment (Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County Kiowa Fraction NW 1/4 NW 1/4 NW 1/4 Section number 16 Township number T 28 S Range number R 18 W	
2. Distance and direction from nearest town or city: 1/2 NW City Limits Street address of well location if in city: Greensburg Kansas	
3. Owner of well: Howard Kerr R.R. or street: City, state, zip code: Greensburg Kansas	
4. Locate with "X" in section below: Sketch map: <div style="display: flex; align-items: center;"> <div style="margin-right: 20px;"> <p>N</p> <p>W E</p> <p>S</p> <p>1 Mile</p> </div> <div> <p>6. Bore hole dia 8 3/4 in. Completion date 12-28-77 Well depth 120 ft.</p> <p>7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary</p> <p>8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input checked="" type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other</p> <p>9. Casing: Material Pl Height: Above or below Threaded <input type="checkbox"/> Welded Blue Surface 14 in. RMP <input checked="" type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. 5 in. to 100 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth (page) No. 290</p> </div> </div>	
5. Type and color of material	
	From To
Top Soil	0 2
Hard Dark Grey Clay	2 9
Redish Brown Clay	9 57
Gravel	57 76
Clay - Cream Colored	76 82
Gravel	82 120
10. Screens: Manufacturer's name Swan Flower Plastics Type RMP Dia. 5" Slot gauze 1/4 Length 20' Set between 900 ft. and 120 ft. <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack Yes Size range of material 4-5	
11. Static water level: <input type="checkbox"/> mo./day/yr. 67 ft. below land surface Date <input type="checkbox"/>	
12. Pumping level below land surfaces: 67 ft. after 1 hrs. pumping 10 g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 40 g.p.m.	
13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>	
14. Well head completion: <input type="checkbox"/> Pitless adapter 12 inches above grade	
15. Well grouted? Yes With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 3 ft. to 14 ft.	
16. Nearest source of possible contamination: ft. 40 Direction E Type Hogs Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <input type="checkbox"/> Model number <input type="checkbox"/> HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe <input type="checkbox"/> ft. capacity <input type="checkbox"/> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
(Use a second sheet if needed)	
18. Elevation:	19. Remarks:
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley	
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Carl Kaye Water Well 224 Business name License No. Address Greensburg Kansas Signed Carl Kaye 12-28-77 Date Authorized representative	

T 28 R 18 W Sec 16 NW 1/4 NW 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5