

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 049 KIOWA NW 1/4 SW 1/4 NW 1/4 35 T 28 S R 18 W

Distance and direction from nearest town or city street address of well if located within city?
 1 1/2 EAST, 2 1/2 SOUTH OF GREENSBURG, KS

2 WATER WELL OWNER: AHRENS, WESLEY 015 Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: RR. 1
 City, State, ZIP code: GREENSBURG, KS 67054- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 180 ELEVATION:
 Depth(s) Groundwater Encountered 1. 133 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 133 ft. below land surface measured on mo/day/yr 4 /24/91
 Pump test data: Well water was ft. after hours pumping gpm
 Estimated Yield 100 gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 8.75 in. to 180 ft., and in. to ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 160 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 160 ft. to 180 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 180 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 4 ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: 01 SEPTIC TANK
 Direction from well? NORTH How many feet? 100

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	3	SILT & SAND			
3	75	TAN CLAY			
75	84	05 SAND 17 GRAVEL			
84	96	TAN CLAY			
96	180	05 SAND 17 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 4 /24/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 05/13/91 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse