

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Kiowa	SW ¼ NW ¼ SE ¼	16	T 28 S	R 18 E/W

Distance and direction from nearest town or city street address of well if located within city?

102 E. Kansas, Greensburg

2 WATER WELL OWNER: Southern Plain Coop	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # : P.O. Box 128	Application Number:
City, State, ZIP Code : Lewis, KS 67552	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 99.5 ft. ELEVATION:
	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL ft. below land surface measured on mo/day/yr Pump test data: Well water was NA ft. after hours pumping gpm Est. Yield NA gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 8 in. to 99.5 ft. and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Air sparge Was a chemical/bacteriological sample submitted to Department? Yes.....No ☒ : If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No ☒

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below) Welded
2 PVC	4 ABS	7 Fiberglass	Threaded. ☒
Blank casing diameter 2 in. to 97.5 ft. Dia. in. to ft. Dia. in. to ft.			
Casing height above land surface 0 in., weight lbs./ft. Wall thickness or gauge No. Sch. 40			
TYPE OF SCREEN OR PERFORATION MATERIAL	7 PVC	10 Asbestos-cement	
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 Drilled holes
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify)
SCREEN-PERFORATED INTERVALS: From 97.5 ft. to 99.5 ft. From ft. to ft.			
GRAVEL PACK INTERVALS: From 94.5 ft. to 99.5 ft. From ft. to ft.			

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other Concrete
Grout Intervals: From 0 ft. to 3 ft. From 3 ft. to 84 ft. From 84 ft. to 94.5 ft.				
What is the nearest source of possible contamination:	1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	14 Abandoned water well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	15 Oil well/Gas well
Direction from well?			13 Insecticide storage	16 Other (specify below)
			How many feet?	

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	0.5	Concrete,	70	76	Sand (vf-c) w/f-m gravel, subrounded, Greenish
0.5	1	Sand (fill),	76	84	Sand (vf-c) w/f-m gravel, Gray
1	5	Clay, silty, moist, plastic, no odor, Brown	84	90	Sand (vf-c) w/f-m gravel, saturated, Grayish B
5	11	Sand (vf-f), v. silty, sl. moist, no odor, Reddish			
11	14	Clay, sandy, moist, no odor, Yellowish Brown			
14	16	Sand (vf-f), silty, no odor, Yellowish Brown			
16	21	Clay, sandy, silty, no odor, Yellowish Brown w			
21	28	Silt, sandy (vf), sl. moist, no odor, Yellowish B			
28	34	Sand (vf-f), silty, sl. moist, Yellowish Brown			
34	44	Silt, sandy (vf), sl. moist, Lt. Grayish Brown			
44	49	Clay, silty, sl. moist, sl. old gas odor, Gray			
49	51	Sand (vf-m), clayey, sl. moist, Grayish Brown			
51	60	Clay, Reddish Brown w/white calcareous mate			AS11, Tag # 00373449, Flushmount
60	64	Sand (vf-f), v. sl. moist, sl. old gas odor, Brown			Project Name: GF - Farmer's Grain Supply
64	70	Sand (vf-f), sl. silty, sl. moist, Greenish Brown			GeoCore # 1322, KDHE # U1 049 00461

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 11/28/2006 and this record is true to the best of my knowledge and belief.
Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) 12/27/2006 under the business name of GeoCore, Inc. by (signature) 12/27/06