

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: **KIOWA** NC 1/4 1/4 SW 1/4 25 T 28 S R 18 W

Distance and direction from nearest town or city street address of well if located within city?
APPROX. 1/2 MILE S, 2 1/2 E, 3/4 S & 1/4 E OF GREENSBURG

2 WATER WELL OWNER: **KELLER, WM. LIVING TRUST**
 RR#, St. Address, Box #: **RT 1** Board of Agriculture, Division of Water Resources
 City, State, ZIP code: **GREENSBURG, KS 67054-9801** Application Number: **26,113**

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL **175** ELEVATION: **0**
 Depth(s) Groundwater Encountered 1. **0 ft.** 2. **0 ft.** 3. **0 ft.**
 WELL'S STATIC WATER LEVEL **110 ft.** below land surface measured on **mo/day/yr 04/18/98**
 Pump test data: Well water was **129 ft.** after **4** hours pumping **1495 gpm**
 Estimated Yield **1495 gpm**: Well water was **0 ft.** after **0** hours pumping **0 gpm**
 Bore Hole Diameter **24** in. to **175 ft.**, and in. to **0 ft.**
 WELL WATER TO BE USED AS: **02 IRRIGATION**
 Was a chemical/bacteriological sample submitted to department? **No** ;
 If yes, mo/day/yr sample was submitted Water well disinfected? **Yes**

5 TYPE OF BLANK CASING USED: **01 STEEL** CASING JOINTS: **GLUED**
 Blank casing diameter **16** in. to **175 ft.**, Dia in. to **0 ft.**, Dia in. to **0 ft.**
 Casing height above land surface **12** in., weight **39 lbs/ft.** Wall thickness or gauge No. **.230**
 TYPE OF SCREEN OR PERFORATION MATERIAL: **01 STEEL**
 SCREEN OR PERFORATION OPENINGS ARE: **01 CONT. SLOT**

SCREEN PERFORATED INTERVALS: From **135 ft.** to **165 ft.**, From **0 ft.** to **0 ft.**
 From **0 ft.** to **0 ft.**, From **0 ft.** to **0 ft.**
 GRAVEL PACK INTERVALS: From **20 ft.** to **175 ft.**, From **0 ft.** to **0 ft.**
 From **0 ft.** to **0 ft.**, From **0 ft.** to **0 ft.**

6 GROUT MATERIAL **03 BENTONITE**
 Grout Intervals: From **0 ft.** to **20 ft.**, From **0 ft.** to **0 ft.**, From **0 ft.** to **0 ft.**
 What is the nearest source of possible contamination: **14 ABAND. WELL**
 Direction from well? **NORTH** How many feet? **225**

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	02 SILT			
3	35	01 CLAY 04 SANDY CLAY			
35	42	05 SAND 01 CLAY			
42	57	01 CLAY			
57	67	05 SAND 11 GRAVEL			
67	74	01 CLAY			
74	116	05 SAND 11 GRAVEL			
116	118	01 CLAY 20 LIMESTONE			
118	165	05 SAND 11 GRAVEL			
165	176	01 CLAY 20 LIMESTONE 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) **04/14/98** and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. **145** This Water Well Record was completed on (mo/day/yr) **04/28/98** under the business name of **HENKLE DRILLING & SUPPLY** by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: KIOWA NC 1/4 1/4 SW 1/4 25 T 28 S R 18 W

2 WATER WELL OWNER: KELLER, WM. LIVING TRUST
RR#, St. Address, Box #: RT 1 Board of Agriculture, Division of Water Resources

City, State, ZIP code : GREENSBURG, KS 67054-9801 Application Number: 26,113

FROM	TO	LITHOLOGIC LOG
176	180	01 CLAY

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/14/98 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/28/98 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichmuth*