

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number  
 COUNTY: *Kiowa* | NE 1/4 NW 1/4 NE 1/4 | 18 | T 28 S | R 18 W

Distance and direction from nearest town or city street address of well if located within city?  
 1 W. OF GREENSBURG, KS

2 WATER WELL OWNER: **KENNETH RICE** *307*  
 RR#, St. Address, Box #: RR. Board of Agriculture, Division of Water Resources  
 City, State, ZIP code : GREENSBURG, KS 67054- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 140 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 82 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 82 ft. below land surface measured on mo/day/yr  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 8.75 in. to 140 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 01 DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 120 ft., Dia in. to 0 ft.; Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 26  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 120 ft. to 140 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 140 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: CATTLE PASTURE  
 Direction from well? ALL How many feet? 4

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	64	TAN CLAY			
64	82	05 SAND AND 17 GRAVEL			
82	86	TAN CLAY			
86	134	05 SAND AND 17 GRAVEL			
134	140	TAN CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 1 /23/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 01/28/95 under the business name of CARL HAYSE WATER WELL SVC by (signature) *Carl Hayse*