

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: IOWA SE 1/4 SW 1/4 SE 1/4 10 T 28 S R 19 W

Distance and direction from nearest town or city street address of well if located within city?  
 4 1/2 MILES EAST, 2 MILES NORTH, 3/4 MILE EAST

2 WATER WELL OWNER: PAULY, DENNIS Board of Agriculture, Division of Water Resources  
 RR#, St. Address, Box #: RT. 1 BOX 150A  
 City, State, ZIP code: GREENSBURG, KS 67054- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

NW	NE	SE	SW
X			

4 DEPTH OF COMPLETED WELL 148 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 75 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 75 ft. below land surface measured on mo/day/yr 11/20/01  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 8.75 in. to 148 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: LIVESTOCK  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 138 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 26  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 138 ft. to 148 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 24 ft. to 148 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout Intervals: From 0 ft. to 24 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: LATERAL LINES  
 Direction from well? WEST How many feet? 4000

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	12	SILT AND SAND			
12	28	TAN CLAY			
28	38	SAND			
38	49	TAN CLAY			
49	148	SAND AND GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/20/01 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 11/21/01 under the business name of DAN HAYSE WATER WELL SVC. by (signature) *Dan Hayse*