

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 049 IOWA SE 1/4 NE 1/4 SE 1/4 6 T 28 S R 19 W

Distance and direction from nearest town or city street address of well if located within city?
 2 1/2 E., 3 1/2 N. OF MULLINVILLE, KS.

2 WATER WELL OWNER: GLEN HARRIS 255 Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: RT.1
 City, State, ZIP code: MULLINVILLE, KS 67109- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 130 ELEVATION:
 Depth(s) Groundwater Encountered 1. 69 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 69 ft. below land surface measured on mo/day/yr
 Pump test data: Well water was ft. after hours pumping gpm
 Estimated Yield gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 8.75 in. to 130 ft., and in. to ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 109 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 109 ft. to 130 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 130 ft. to 25 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 4 ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: 01 SEPTIC TANK
 Direction from well? NW How many feet? 150

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	40	TAN CLAY			
40	108	05 SAND AND 17 GRAVEL			
108	110	TAN CLAY			
110	127	05 SAND AND 17 GRAVEL			
127	130	WHITE CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 2 /7 /94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 02/09/94 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse