

WATER WELL RECORD Form WWC-5 KSA 82a-1212

268

1 LOCATION OF WATER WELL: Fraction NW 1/4 SE 1/4 SE 1/4 Section Number 3 Township Number T 28 S Range Number R 19 W
 COUNTY: KIOWA

Distance and direction from nearest town or city street address of well if located within city?
 2 MILES NORTH, 4.5 MILES WEST OF GREENSBURG

2 WATER WELL OWNER: TGT PETROLEUM CORP.
 RR#, St. Address, Box #: PO BOX 75097 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: WICHITA, KS 67275-0097 Application Number: 20050332

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 140 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \									
1	--- NW ---	---	NE ---	---	---	---	---	---	---
M	W ---	---	---	---	---	---	---	---	E
i	---	---	---	---	---	---	---	---	---
l	---	---	---	---	---	---	---	---	---
e	---	SW ---	---	SE ---	---	---	---	---	---
\ /	---	---	---	---	---	---	---	---	---

WELL'S STATIC WATER LEVEL 83 ft. below land surface measured on mo/day/yr 01/02/06
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 8.75 in. to 140 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: OIL FIELD
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 120 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 120 ft. to 140 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 140 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 2 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: OIL/GAS WELL
 Direction from well? WEST How many feet? 4000

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	5	SILT AND SAND			
5	9	BROWN CLAY			
9	14	TAN CLAY			
14	16	SAND			
16	54	TAN CLAY			
54	111	SAND AND GRAVEL			
111	116	TAN CLAY			
116	140	SAND AND GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/02/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 01/11/06 under the business name of DAN HAYSE WATER WELL SERV by (signature) Dan Hayse