

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No. 1

11.731

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed, reconstructed, or plugged under my jurisdiction and was completed on (mo/day/year) 7-14-11..... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 208..... This Water Well Record was completed on (mo/day/year) 7-18-11..... under the business name of MINTER-WILSON DRILLING CO., INC...... by (signature) Nora J. Heller.....

INSTRUCTIONS: Use typewriter or ball point pen. **PLEASE PRESS FIRMLY** and **PRINT** clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include **fee** of \$5.00 for each constructed well. Visit us at <http://www.kdheks.org/waterwell/index.html>

The
Professionals

MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 620-276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

NAME FRY FAMILY FARMS
COUNTY GRAY
DATE 6-10-11

LOCATION: NE 1/4 18-28-29 - SALEM CHURCH - 8 MILES EAST, 2 MILES SOUTH
 & 3/4 OF A MILE EAST ON THE SOUTH SIDE
 - 115 FT. EAST OF EXISTING WELL

STATIC WATER LEVEL - 200 FT.

TEST # 2

0' TO 12' - BROWN CLAY
12' TO 28' - BROWN SANDY CLAY WITH STRIPS OF WHITE ROCK
28' TO 44' - FINE TO MEDIUM SAND
44' TO 140' - BROWN SANDY CLAY WITH STRIPS OF WHITE ROCK
140' TO 152' - FINE TO MEDIUM SAND & GRAVEL
152' TO 165' - BROWN SANDY CLAY WITH STRIPS OF WHITE ROCK
165' TO 168' - FINE TO MEDIUM SAND & GRAVEL - SOME COARSE
168' TO 188' - BROWN SANDY CLAY WITH STRIPS OF WHITE ROCK
188' TO 203' - FINE TO MEDIUM SAND & GRAVEL
 WITH STRIPS OF BROWN SANDY CLAY
203' TO 218' - BROWN SANDY CLAY WITH STRIPS OF WHITE ROCK
218' TO 230' - FINE TO MEDIUM SAND & GRAVEL
 WITH STRIPS OF BROWN SANDY CLAY
230' TO 331' - BROWN SANDY CLAY & BROWN CLAY LAYERED
331' TO 347' - FINE TO MEDIUM SAND
347' TO 356' - BROWN SANDY CLAY & YELLOW SANDY CLAY
356' TO 361' - FINE TO MEDIUM SAND WITH A LITTLE BROWN ROCK
361' TO 368' - BROWN SANDY CLAY
368' TO 384' - FINE TO MEDIUM SAND WITH 20% BROWN SANDY CLAY
384' TO 395' - BROWN & YELLOW SANDY CLAY WITH 20% BROWN ROCK
395' TO 401' - BROWN & YELLOW CLAY WITH 35% BROWN ROCK
401' TO 403' - LOOSE BROWN ROCK
403' TO 408' - HARD BROWN CLAY
408' TO 420' - GRAY SHALE & HARD BROWN CLAY
 WITH A FEW STRIPS OF BROWN ROCK - 5%
420' TO 440' - GRAY SHALE - 250 PULL DOWN