

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction SW 1/4 SE 1/4 SE 1/4 Section Number 7 Township Number T 28 S Range Number R 19 W COUNTY: KIOWA

Distance and direction from nearest town or city street address of well if located within city? 2 MILES EAST, 2 MILES NORTH OF MULLINVILLE

2 WATER WELL OWNER: BROWN, SCOTT RR#, St. Address, Box # : 900 EAST KANSAS City, State, ZIP code : GREENSBURG, KS 67054- Board of Agriculture, Division of Water Resources Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 160 ELEVATION: 0 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft. WELL'S STATIC WATER LEVEL 103 ft. below land surface measured on mo/day/yr 09/17/14 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 8.75 in. to 160 ft., and in. to 0 ft. WELL WATER TO BE USED AS: LIVESTOCK Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED Blank casing diameter 5 in. to 140 ft., Dia in. to 0 ft., Dia in. to 0 ft. Casing height above land surface 24 in., weight 0 lbs/ft. Wall thickness or gauge No. 21 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 160 ft., From 0 ft. to 0 ft. From 0 ft. to 0 ft., From 0 ft. to 0 ft. GRAVEL PACK INTERVALS: From 24 ft. to 160 ft., From 0 ft. to 0 ft. From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE Grout Intervals: From 0 ft. to 24 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft. What is the nearest source of possible contamination: SEPTIC TANK Direction from well? NORTH How many feet? 7000

Table with columns: FROM, TO, LITHOLOGIC LOG, FROM, TO, PLUGGING INTERVALS. Rows include: 0-22 SILT AND SAND, 22-61 TAN CLAY, 61-117 SAND AND GRAVEL, 117-144 TAN CLAY, 144-156 SAND AND GRAVEL, 156-160 BROWN ROCK, 160-159 BLUE SHALE.

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/17/14 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 12/04/14 under the business name of DAN HAYSE WATER WELL SERV by (signature) Dan Hayse